

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-065-21,175-00-00

LEASE NAME Turner

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 1

1650 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 7 TWP. 10 RGE. 22 ~~XXXX~~ (W)

COUNTY Graham

Date Well Completed 10/26/79

Plugging Commenced 3/7/87

Plugging Completed 3/10/87

LEASE OPERATOR H-30, Inc.

ADDRESS 251 N. Water, Suite 10, Wichita, KS 67202

PHONE#(316) 263-2043 OPERATORS LICENSE NO. 5107

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? District #6

Is ACO-1 filed? Yes If not, is well log attached? No

Producing Formation Conglomerate Sd. Depth to Top 4070 Bottom 4090 T.D. 4325

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Conglomerate Sd.	Oil	Surface	217	8-5/8"	217	None
		Surface	4235	5-1/2"	4235	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.
See Attached Schedule

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Cheyenne Well Service License No. _____

Address 118 N. Penn, Ness City, KS 67560

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jeffrey A. Burk

(Employee of Operator ~~XXXXXXXXXXXXXXXXXX~~ of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct.

(Signature) _____

(Address) 251 N. Water, Suite 10, Wichita, KS

SUBSCRIBED AND SWORN TO before me this 29th day of July, 19 87 67202
 Wichita, Kansas



Pamela J. Deitchler
 Notary Public

My Commission Expires: June 14, 1990

15-065-21175-00-00

TURNER #1 (Section 7-10S-22W) WORKOVER
DAILY REPORT

- 03/07/87 Cheyenne moved rig in and rigged up on #1 well (should have been #2)
- 03/09/87 Crew arrived at 8:30, broke down connections and started pulling rods. Pumped 40 barrels, heated lease crude (250° F) down tubing and rigged up swab line. Hit tight spot with tubing swab at 850' and could not get through. Pulled tubing and laid out for steamers. SION at 4:30 p.m. Steamers (Guthrie Tank) arrived at 4:45. Finished at 6:30 p.m.
- 03/10/87 Teko Pipe Testing arrived at 6:45 a.m. Tested 126 joints of tubing (45 good, 19 with bad col., 51 with bad threads, 11 with holes). Halliburton arrived at 9:30 a.m. with RTTS Packer to check for holes in casing. Loaded backside and began testing.

820' with 300# (held)
1013' with 300# (held)
1203' with 300# (communicated)
1395' with 300# (communicated)
1450' hit collapsed or parted casing.

Decided to plug well. Called state plugger (Carl Goodrow) and pulled tubing. Plugged with 50 sacks and 2 hulls down the backside and 125 sacks, 3 hulls (Econolite) down 5½" casing. Left 700# on well overnight. Plug down at 8:45 p.m.



Jeffrey A. Burk

cc: Dean
Gary
File

RECEIVED
STATE CORPORATION COMMISSION

07-09-1987
JUL 9 1987

CONSERVATION DIVISION
Wichita, Kansas