

15-065-00619-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 9 Twp. 10S Rge. 22 (X) (W)

Location as "NE/CNW/SW" or footage from lines NE NE NW

Lease Owner: Leben Drilling, Inc.

Lease Name: Griffith Well No. 1

Office Address: 905 Central Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-14-58 19

Application for plugging filed 1-14-58 19

Application for plugging approved 1-14-58 19


Plugging commenced 1-14-58 19

Plugging completed 1-14-58 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well A. D. Fabricius

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	232'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

1st Plug @ 600' w/25 sacks cement
2nd Plug @ 250' w/15 sacks cement
Top Plug @ 40' w/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1958
01-18-1958
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Leben Drilling, Inc.

Address: 905 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. James M. Battin (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James M. Battin
905 Central Bldg., Wichita
(Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 19 58

June 17, 1961

Ruth N. Benjamin
Ruth N. Benjamin Notary Public.



PLUGGING
FILE SEC 9 T 10 R224
BOOK PAGE 76 LINE 42

WELL LOG

COMPANY: LEBEN DRILLING, INC.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: GRIFFITH #1
 LOCATION: NE NE NW 9-10S-22W,
 GRAHAM COUNTY, KANSAS
 COMMENCED: JANUARY 3, 1958
 COMPLETED: JANUARY 14, 1958

0	440	Shale & Shells	
440	930	Shale & Limestks.	TOPS:
930	1010	Sand & Shale	Anhydrite 1840
1010	1125	Shale & Shells	Topeka 3328
1125	1200	Sand	Heebner 3548
1200	1310	Shale & Shells	Toronto 3572
1310	1590	Sand	Lansing-KC 3586
1590	1840	Redbed	Base K.C. 3812
1840	1860	Anhydrite	Elevation 2323 K.F.
1860	1881	Anhydrite	
1881	2010	Shale & Lime stks.	
2010	2300	Shale & Shells	
2300	2835	Lime & Shale	
2835	3525	Shale & Lime	
3525	3548	Lime & Shale	
3548	3552	Heebner	
3552	3590	Lime & Shale	
3590	3812	Lime	
3812	3832	Shale & Lime	
	<u>3832</u>	<u>Rotary Total Depth - D & A</u>	

STATE OF KANSAS
 JAN 17 1958
 01-18-1958
 COUNTY OF SEDGWICK

Set 232' of 8 5/8" surface casing with 150 sacks cement & 3% CaCl.

I, James M. Battin, do hereby certify that the above and foregoing is a true and correct copy of the log of the Griffith #1, NE 1/4 NE 1/4 NW 1/4 Section 9, Township 10 South, Range 22 West, Graham County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC.

By: James M. Battin

State of Kansas }
 County of Sedgwick) SS:

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, on this 17th day of January, 1958.

Ruth N. Benjamin
 Ruth N. Benjamin, Notary Public

My Commission Expires: 6-17-61.

PLUGGING
 SEC 9, T. 10, R. 22W
 BOOK PAGE 76 LINE 42