

15-065-00055-00-01

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1983
8966

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Graham SEC. 11 TWP. 10 S. RGE. 22 N/W
Location as in quarters or footage from lines:
C. SE SE SE

Lease Owner Calvin Noah (Lic. # 5616)
Lease Name Dorothy Horn Well No. 1
Office Address 329 N. Birch, Valley Center, Ks 67147
Character of Well (Completed as Oil, Gas or Dry Hole): Oil
Date Well Completed Rotary Completion 9-22-1980 (OWWO)
Application for plugging filed 11-10-82 was Western Drig. #1 Johnson
Plugging commenced 1-18-1983
Plugging completed 1-19-1983
Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Non Commercial
Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Carl Goodrow
Producing formation Marmaton Depth to top 3854 bottom 3876 T.D. 4021
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface Casing		0	214	10"	214'	None
Production		0	4016	4 1/2"	4016	1797'
Show oil 3854-3876	Marmaton					
Small show oil 3726-3728	Lansing-Kc.					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped 2 sacks of cottonseed hulls, 20 sacks of Gel, 100 sacks of 50/50 pozmix cement, 6 % Gel, 3 % Calcium Chloride, 7 more sacks of Gel and then followed by 75 more sacks of cement. Maxim. PSI 500 lbs. and shut-in at 100 PSI. (above as per KCC Agent's instructions.)

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Pfeifer Well Service, Inc.
(Cemented by Allied Cementing Co)

STATE OF Kansas COUNTY OF Sedgwick, ss.
Calvin Noah (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) Calvin Noah
329 N. Birch, Valley
(Address)
Center, Kansas 67147

9TH day of FEB, 1983.
V. S. Jerney
Notary Public.

SUBSCRIBED AND SWORN TO before me this _____
My Commission expires: Nov. 23, 1984




WELL DRILLING RECORD

15-065-00055-00-01

FORMATION PLUG

LOG



Johnson #1

January 15, 1947

SE, SE 1/4, Section 11, Township 10 South, Range 22 West

Graham County, Kansas

Drilled by

THE WESTERN DRILLING COMPANY, INC.

315 DERBY BUILDING WICHITA 2, KANSAS

COMPANY TOOLS

Commenced - December 18, 1946

Completed - January 13, 1947

Surface and Shale	138'
Shale and Shells	650'
Broken Lime and Sand	840'
Sand	855'
Redbed	910'
Sand	970'
Shale and Shells	1065'
Sand	1080'
Shale and Shells	1200'
Sandy Lime	1233'
Shale and Shells	1340'
Sand	1530'
Shale	1560'
Shale and Shells	1785'
Chalky Lime	1810'
Lime	2350'
Shale	2520'
Shale and Shells	2555'
Lime	2645'
Shale and Shells	2660'
Lime	2765'
Shale and Shells	2776'
Lime	3435'
Shale and Shells	3785'
Lime	3880'
Shale and Shells	3889'
Chert	3910'
Conglamert	3961'
Chert	3978'
Simpson Shale	4021'

Arbuckle Lime be addressed to The Western Drilling Co., Inc. 315 Derby Building, Wichita, Kansas, D. & A.

STATE OF KANSAS COUNTY OF ...


Casing Record - 10-3/4" 214' 150 sacks

315 Derby Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 17th day of January, 1947

Vivian J. Yinger Notary Public

November 29, 1950



15-065-00055-00-01

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

OIL

Calvin Noah

Well No.

1

Lease Name

Dorothy D, Horn

S 11 T 10 R 22 E W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<u>New Log Tops</u>				
Topeka	3314	(-1019)		
Heebner	3524	(-1229)		
Toronto	3547	(-1252)		
Lansing	3562	(-1267)		
BKC	3781	(-1486)		
Pawnee Lm	3854	(-1559)		
Cgl. Cheft	3908	(-1613)		
Arbuckle	3976	(-1681)		
RTD	4020	(-1725)		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

Calvin Noah

Signature

operator

Title

1-23-81

Date