

STATE OF KANSAS  
STATE CORPORATION COMMISSION


15-045-00345-00-00

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Biting Building  
Wichita, Kansas

Graham County, Sec. 16 Twp. 10 Rge. 22 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NE NE NE  
Lease Owner National Cooperative Refinery Association  
Lease Name Griffith Well No. 1  
Office Address 820 Union National Bank Building  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 4, 19 52  
Application for plugging filed March 5, 19 52  
Application for plugging approved March 6, 19 52  
Plugging commenced March 6, 19 52  
Plugging completed March 6, 19 52  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Eldon Petty, Hays, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4031 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	154'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.  
Filled hole with heavy mud to 154', set plug, dumped 15 sacks cement. Filled hole with heavy mud to 140', set plug / 1/2 sx. hulls, dumped 10 sacks cement on up to base of cellar.

STATE CORPORATION COMMISSION  
MAR 11 1952  
CONS. DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor West Supply Company  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
W. Jean La Coss (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. Jean La Coss  
820 Union National Bank Building  
(Address)

SUBSCRIBED AND SWORN to before me this 10 day of March, 1952  
I. A. Lange Notary Public.

My commission expires February 20, 1953 23-8390-s 6-51-20M

PLUGGING  
FILE SEC 16 T 10 R 22  
BOOK PAGE 148 LINE 21

15-065-00345-00-00

COPY

DRILLER'S LOG NO. 1 GRIFFITH

National Cooperative Refinery Assoc., Lease  
Owner

Section 16, Twp. 10S, Rge. 22W

Garvey Drilling Company, Contractor

Location: NE NE NE

Drilling Commenced: February 22, 1952

County: Graham

Drilling Completed: March 4, 1952

Production: D & A

Casing Record: 8 5/8" @ 154' w/90 sax

R.T.D.: 4031'

FIGURES BELOW INDICATE BOTTOM OF FORMATION:

85	Sand & Shale
705	Shale & Shells
930	Sand Streaks
1075	Sand
1775	Shale & Shells
1820	Anhydrite
2260	Shale & Shells
2750	Shale & Lime
3050	Shale & Shells
3195	Shale, Shells & Lime
3495	Shale & Lime
3785	Lime
3955	Conglomerate
3973	Lime
4000	Conglomerate & Arbuckle Lime
4031	Lime

Tops:

Heebner:	3500 (-1240)
Lansing:	3538 (-1278)
Arbuckle:	3965 (-1705)

Plugging Record:

Mudded up to 150' and set wooden plug at 150'. Cemented with 15 sax cement on top of plug. Mudded up to 40' and set second wooden plug at 40'. Placed 10 sax cement on top of plug.

4031' R.T.D.

I hereby certify that this is a true and correct log of the above mentioned well.

Garvey Drilling Company

By W. W. Fisher /s/  
W. W. Fisher

State of Kansas )  
                  ) SS:  
County of Sedgwick )

STATE COMMISSION  
MAR 14 1952  
CORR. 03-14-1952

Subscribed to and sworn to before me, a Notary Public, in said County and State, this 12th day of March, 1952.

Charlotte Weidman  
Notary Public

My commission expires: October 13, 1954.