

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,296

LEASE NAME GRIFFITH 00-00

WELL NUMBER 1

SPOT LOCATION NE SE SW

SEC. 16 TWP. 10 RGE. 22 (E) or (W)

COUNTY GRAHAM

Date Well Completed 2-24-86

Plugging Commenced 2-24-86

Plugging Completed 2-24-86

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R P NIXON OPERATIONS

ADDRESS 207 W 12TH HAYS KS 67601

PHONE # (913) 628-1316 OPERATORS LICENSE NO. 5252

Character of Well DRY
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS GIB SCHECK

Is ACO-1 filed? YES If not, is well log attached? YES

Producing formation _____ Depth to top _____ bottom _____ T.D. 4100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled out |
|----------------|---------|-------------|-------------|---------------|-------------|-------------|
| <u>SURFACE</u> | | <u>204'</u> | <u>surf</u> | <u>8 5/8"</u> | <u>204'</u> | <u>NONE</u> |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Cement with 200 sx 60/40 pozmix 6% gel 1 sack flowseal
20 sacks in Arbuckle (4050'), 20 sacks @ 1900', 100 sacks plus one sack
flowseal @ 1050', 40 sacks @ 250', solid plug & 10 sacks @ 40' and 10
sacks in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor JAY-LAN CORPORATION License No. 719
Address 207 W 12TH HAYS KS 67601

STATE OF KANSAS COUNTY OF ELLIS, ss.

DAN NIXON (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) [Signature]

(Address) 207 W 12TH HAYS KS 67601

SUBSCRIBED AND SWORN TO before me this 25 day of FEBRUARY, 1986

LORNA M. HERRMAN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 6-19-88

Lorna M Herrman
Notary Public
STATE CORPORATION COMMISSION

FEB 27 1986
02-27-1986
CONSERVATION DIVISION

Form CP-4 /-54
Revised 06-83

My Commission expires: