

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-21,232-0001

LEASE NAME Webster

RECEIVED

05-08-2003  
MAY 08 2003

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 2

440 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 16 TWP. 10S RGE. 22W (E) or (W)

COUNTY Graham

Date Well Completed 6/1980

Plugging Commenced 4/14/03

Plugging Completed 4/14/03

**KCC WICHITA**

LEASE OPERATOR Ritchie Exploration, Inc.

ADDRESS P.O. Box 783188

PHONE# (316) 691-9500 OPERATORS LICENSE NO. 4767

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on April 14 2003 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? yes If not, Is well log attached? \_\_\_\_\_

Producing Formation L/KC Depth to Top 3737 Bottom 3778 T.O. 4050'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>L/KC</u>	<u>brine/oil</u>	<u>3601</u>	<u>3821</u>	<u>8 5/8"</u>	<u>173</u>	<u>n/a</u>
				<u>4 1/2"</u>	<u>4046</u>	<u>n/a</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each sat.

Perforate casing at 1900' and 1025' w/2 SPF. Ran tubing to 2125'. Pumped 125 sacks 60/40 poz with 10% gel, 300# hulls down tubing. Cement circulated to surface up 4 1/2" casing. Pulled tubing out of hole. Pumped 100 sacks 60/40 poz with 10% gel, 200# hulls down 8 5/8" casing. Pumped 55 sacks 60/40 poz with 10% gel, 100# hulls down 4 1/2 casng. Plugging complete at 11:00 a.m.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing, Inc. License No. \_\_\_\_\_

Address PO Box 31 Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Ritchie Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

John C. Niernberger (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) PO Box 783188  
Wichita, KS 67278-3188

SUBSCRIBED AND SWORN TO before me this 7th day of May, 19 2003

My Commission Expires: \_\_\_\_\_

**KAREN HOPPER**  
Notary Public - State of Kansas  
My Appt. Expires 10/22/03