

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 03/92

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

API # 15-065-22,727-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Satex Energy, Inc. KCC LICENSE # 31342

ADDRESS 100 NE Loop 410 Suite 1380 (owner/company name) CITY San Antonio (operator's)

STATE Texas ZIP CODE 78216 CONTACT PHONE # (210) 366-1380

LEASE Parks WELL# 1 SEC. 34 T. 10S R. 21 (East/West)

-SW - NE NW SPOT LOCATION/QQQQ COUNTY Graham

990' FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1420' FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 312' CEMENTED WITH 60-40 posmix-230 sx SACKS

PRODUCTION CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: _____

ELEVATION 2107'/2202' T.D. 3847' PBDT _____ ANHYDRITE DEPTH 1688'-1712'
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Fill w/heavy mud; set 1st plug @ 3800' w/25 sx; 2nd plug @ 1690' w/25 sx; 3rd plug @ 900' w/100 sx; 4th plug @ 360' w/40 sx; 5th plug @ 40' w/10 sx; rathole 15 sx; Total 250 sx; 60-40 posmix 6% gel 2 sx celoflake.
(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? No

If not explain why? Sent to Operator to complete.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Gary Fisher PHONE# (913) 743-5654

ADDRESS P.O. Box 103 City/State Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie RTD, Inc. KCC LICENSE # 30684

(company name) (contractor's)
ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Complete @ 12:15 p.m. 11-18-93

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR/AGENT

DATE: 11-24-93 AUTHORIZED OPERATOR/AGENT: [Signature]

Rec'd 12-16-93
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
KANSAS