

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. MARKET, ROOM 2078  
WICHITA, KS 67202

WELL PLUGGING RECORD  
K.A.R. -82-3-117

API NUMBER 15-065-03130-0000

LEASE NAME Anderson A

WELL NUMBER #1

990 Ft. from S Section Line  
4950 Ft. from E Section Line

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

SEC. 3 TWP. 10S RGE. 24W (E) or (W)

COUNTY Graham

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd St. N., Bldg. 300, Wichita, KS 67226

PHONE # (316) 682-1537 OPERATOR'S LICENSE NO. 5030

Date Well Completed 10/3/61

Character of Well OIL

Plugging Commenced 3/20/00

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 3/20/00

The plugging proposal was approved on 03/20/2000 (date)  
by Dennis Hamel (KCC District Agent's Name)

Is ACO-1 filed? na If not, is well log attached? yes

Producing Formation LKC Depth to Top 3981' Bottom 3985 T.D. 3992

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS		Casing Record				
Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	204	-----
				5-1/2"	4039	-----

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Connected to 5-1/2" csg and pumped as follows: 35 sx 60/40 Poz w/10% gel and 200# hulls, then 22 sx gel; then 215 sx same cement w/250# hulls. Max press. 600#, SIP - 200#.

Connected to 8-5/8" and 5-1/2" annulus and pumped 25 sx same cement w/100# hulls.

Approved by Dennis Hamel w/KCC

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. \_\_\_\_\_

Address P.O. Box 31- Russell, KS 67665-0031

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joel Stull

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Pat Canaday (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says that: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature)


(Address)

SUBSCRIBED AND SWORN TO before me this

8100 E. 22nd St. N., Bldg. 300  
Wichita, KS 67226

4th day of April 2000

Michelle D. Henning  
Notary Public



My Commission Expires:



RECEIVED  
STATE CORPORATION COMMISSION

APR 6 2000  
04-06-2000  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG

OPERATOR C-G Drilling Co. & Houston Petroleum Co. 3-10-24  
 WELL NAME Anderson "A" #1 NW SW SW  
 TOTAL DEPTH 4040' Graham  
 COMP. September 19, 1961 SEP. September 30, 1961 Kansas  
 RIG NO. 2 ELEVATION 2460' R.B.  
 CASING: Ran 201.21' (11 jts.) 8-5/8" OD Surface PRODUCTION: Producing  
 Casing.  
 Set 5-1/2" OD Casing @4039' (106 jts.)

All measurements taken from the top of casing head

FROM	TO	FORMATION	VERTICAL	REMARKS
0	204	Shale & Sand		
204	1580	Shale		
1580	1865	Sand		
1865	2092	Red Bed		
2092	2135	Anhydrite		
2135	2470	Shale & Shells		
2470	2565	Shale & Shell	00 - 2500	
2565	2775	Shale & Shells	00 - 2750	
2775	3085	Lime & Shale	00 - 3000	
3085	3280	Shale & Lime	00 - 3250	
3280	3380	Lime & Shale		
3380	3700	Shale & Lime	00 - 3500	
3700	3807	Lime & Shale	00 - 3750	DST 3777-3807'
3807	4040	Lime		DST 3906-3924'
				DST 3932-3952'
				DST 3948-3972'
				DST 3968-3994'

RECEIVED STATE CORPORATION COMMISSION

APR 6 2000 04-06-2000 CONSERVATION DIVISION Wichita, Kansas

STATE OF KANSAS }  
COUNTY OF SEDGWICK } SS.

The undersigned hereby certifies that to the best of his knowledge and belief, the above is a true and correct...

C-G DRILLING CO.  
G. F. Galloway  
December 7th, 1961  
Lucky Jacobs

WELL LOG  
SUBSCRIBED AND SWORN TO before me this 7th day of December, 1961.  
My commission expires  
MAY 10, 1963

# ALLIED CEMENTING CO., INC. 3781

Federal Tax I.D.#

REMIT TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

15-065-03130-00-00

Oakley

DATE 3-20-00	SEC. 3	TWP. 10 <sup>s</sup>	RANGE 24 <sup>w</sup>	CALLED OUT	ON LOCATION 3:00 PM	JOB START	JOB FINISH 5:00 PM
LEASE Anderson		WELL # A-1	LOCATION St Peter SE-1/4N-E.S.	COUNTY Graham	STATE Kan		
<input checked="" type="radio"/> OLD OR NEW (Circle one)							

CONTRACTOR None

TYPE OF JOB Old Hole Plug

HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_

CASING SIZE 5 1/2 DEPTH \_\_\_\_\_

TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_

DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_

TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_

PRES. MAX 600# MINIMUM 200#

MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_

CEMENT LEFT IN CSG. \_\_\_\_\_

PERFS. \_\_\_\_\_

DISPLACEMENT \_\_\_\_\_

OWNER Same

CEMENT

AMOUNT ORDERED 275 sks 60/40 pm  
10% Gel, 22-Gel, 500# Hulls

COMMON	16.5 sks @ 6.35	1,047.25
POZMIX	110 sks @ 3.25	357.50
GEL	46 sks @ 9.50	437.00
CHLORIDE	@	
Hulls	5 sks @ 15.50	77.50
	@	
	@	
	@	
	@	
HANDLING	275 sks @ 1.05	288.75
MILEAGE	4¢ per sk/mile	660.00
TOTAL		2,868.50

EQUIPMENT

PUMP TRUCK CEMENTER Walt

# 191 HELPER Dean

BULK TRUCK DRIVER Andrew

# 218 DRIVER \_\_\_\_\_

BULK TRUCK DRIVER \_\_\_\_\_

REMARKS:

Hook up to 5 1/2 casing, mix 35 sks w/ 200# Hulls, 22 sks Gel, 215 sks w/ 250# Hulls & 600# max, shut in & 200# mix 25 sks w/ 50# Hulls down Annals

SERVICE

DEPTH OF JOB \_\_\_\_\_

PUMP TRUCK CHARGE \_\_\_\_\_ 450.00

EXTRA FOOTAGE @ \_\_\_\_\_

MILEAGE 60 mile @ 3.00 180.00

PLUG @ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

TOTAL 630.00

CHARGE TO: Vess Oil Corp

STREET \_\_\_\_\_

CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

FLOAT EQUIPMENT

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

@ \_\_\_\_\_

TOTAL \_\_\_\_\_

To Allied Cementing Co., Inc.  
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

TAX \_\_\_\_\_

Sol TOTAL CHARGE ~~6909.80~~

DISCOUNT -524.78 IF PAID IN 30 DAYS

Total = 2900.00

SIGNATURE [Signature]

PRINTED NAME RECEIVED  
STATE CORPORATION COMMISSION

APR 6 2000

CONSERVATION DIVISION  
Wichita, Kansas