

15-065-02120-00-00

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Graham County, Sec. 7 Twp. 10S Rge. 24W (E) (W)

Location as "NE/CNW/SW" or footage from lines C NE NE

Lease Owner Imperial Oil Company

Lease Name RICHMEIER "A" Well No. 1

Office Address 780 Fourth Natl. Bldg., Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed May 7, 1962 19

Application for plugging filed May 7, 1962 19

Application for plugging approved May 7, 1962 19

Plugging commenced May 7, 1962 19


Plugging completed May 7, 1962 19

Reason for abandonment of well or producing formation

No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4038 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: FORMATION, CONTENT, FROM, TO, SIZE, PUT IN, PULLED OUT. Row 1: Surface Casing - 8-5/8" at 222' not pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set first plug at 550' with 20 sacks cement.

Set second plug at 200' with 20 sacks cement

Set top plug at 40' with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 14 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
05-14-1962

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Imperial Oil of Kansas, Inc.

Address Box 97, WaKeeney, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

John Lehman (employee of owner) or (owner/operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John Lehman

780 Fourth National Bldg., Wichita, Ks.

(Address)

Subscribed and sworn to before me this 11th day of May, 1962

My commission expires July 27, 1964

Bette J. Behymer Notary Public.



15-065-02120-00-00

DRILLER'S LOG

Imperial Oil Company  
780 Fourth National Building  
Wichita, Kansas

RICHMEIER "A" NO. 1  
C NE NE Sec. 7-10S-24W  
Graham County, Kansas

Total Depth: 4038'

Elevation: 2483 K.B.  
Production: Dry

Commenced: 4/28/62 Completed: 5/7/62

Contractor: Imperial Oil of Kansas, Inc.  
Wichita 2, Kansas

Casing Record: Set 8-5/8" surface pipe at 222' with 160 sacks cement.

Figures indicate bottom of formations:

TOPS

Surface Clay & Sand	222'	Heebner	3764 (-1281)
Shale & Sand	1680'	Toronto	3787 (-1304)
Dakota Sand	1880'	Lansing - K.C.	3799 (-1316)
Shale & Shells	2125'	Base Kansas City	4034 (-1551)
Anhydrite	2160'	Rotary Total Depth	4038 (-1555)
Shale & Shells	2565'		
Shale & Lime	2880'		
Shale	2915'		
Lime & Shale	3065'		
Lime	3170'		
Lime & Shale	3735'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL COMPANY

By Raymond R. Dombaugh  
Raymond R. Dombaugh

Subscribed and sworn to before me this 14th day of May, 1962.

My Commission Expires:

July 27, 1964

Bette J. Behymer  
Bette J. Behymer, Notary Public

