

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22204-00-60

LEASE NAME Riedel

WELL NUMBER 1

SPOT LOCATION S/2 SW NW

SEC. 7 TWP. 10 RGE. 24 ~~XXXX~~ (W)

COUNTY Graham

Date Well Completed 8-8-1985

Plugging Commenced 8-8-1985

Plugging Completed 8-8-1985

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR T-L Energy

ADDRESS St. Peter Route, Morland, Ks. 67650

PHONE # (913) 627-5711 OPERATORS LICENSE NO. 8714

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays Office

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4010

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Surface		0	217	8 5/8"	217	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

1st Plug set at 2110' with 30 sacks common cement 60-40 Poz 6%Gel 3%Cal cl.

2nd. Plug set at 1230' with 100 sacks common cement 1 sack cello flake 6%Gel 3%Cal cl.

3rd. Plug set at 240' with 50 sacks common cement 6%Gel 3%cal cl.

4th Plug set at 40' with 10 sacks common cement 6%Gel 3%Cal cl.

10 sacks in rathole

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan License No. _____
Address Hays, Ks. 67601

STATE OF Kansas COUNTY OF Graham, ss.

Jerry M. Helberg (employee of operator) or
(operator) of above-described well, being duly sworn on oath, says: That I have knowledge of the facts, STATE CORPORATION COMMISSION
and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
SEP 26 1985

09-26-1985
CONSERVATION DIVISION
Wichita, Kansas

(Signature) Jerry M. Helberg
(Address) Box 32 Morland, Ks. 67650

SUBSCRIBED AND SWORN TO before me this 21 day of August, 1985

Janice Richman
Notary Public

