

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County. Sec. 8 Twp. 10 Rge. 24 (E) (W) X

Location as "NE/CNW/SW" or footage from lines C of NE NE

Lease Owner Imperial Oil of Kansas, Inc.

Lease Name Dreiling "B" Well No. #1

Office Address Box 97, Wakeeney, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 5-22-62 19

Application for plugging approved 19


Plugging commenced 6-5-62 19

Plugging completed 6-9-62 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced?



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4063' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Production packer for bottom hole plug at 3970'
Circulated hole with 18 sacks gel and spotted 20 sacks cement at 550'. Pulled 12 joints.
Spotted 20 sacks cement at 180'. Pulled 6 joints.
Mudded hole back to 35' and sat 5' rock bridge. Mixed and dumped 10 sacks cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 12 1962
06-12-1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas


STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 11 day of June, 1962

My commission expires 24 October 1964

Sidney D. Miller
Notary Public.



15-065-03133-00-00

RECEIVED
STATE CORPORATION COMMISSION

MAY 24 1962
05-24-1962
CONSERVATION DIVISION
Wichita, Kansas

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

Dreilling "B" No. 1
C NE NE Sec. 8-10S-24W
Graham County, Kansas

Total Depth: 4063'

Elevation: 2488' K.B.
Production:

Commenced: 3-28-60 Completed: 4-7-60

Contractor: Imperial Oil of Kansas, Inc.
Wichita 2, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 219' with 175 sacks of cement.
Set 4-1/2" Production Pipe at 4062' with 75 sacks of cement.

Figures indicate bottom of formations:

		<u>TOPS</u>	
Surface Clay	130'		
Shale	219'	Anhydrite	2134' (/ 354)
Shale & Sand	560'	Heebner	3782' (-1294)
Shale, Sand & Shells	1530'	Toronto	3805' (-1317)
Shale, Sand & Redbeds	2133'	Lansing	3820' (-1332)
Anhydrite	2169'	Base/Kansas City	4064' (-1558)
Shale & Shells	2585'	Total Depth	4063' (-1575)
Shale & Lime	3760'		
Lime	4063'		
Total Depth	4063'		

We hereby certify this to be a correct and accurate log of the above described well, as shown on the daily drilling reports.

IMPERIAL OIL OF KANSAS, INC.

By: *K. J. Boone*
K. J. Boone - Pet. Engr.

Subscribed and sworn to before me this 19th day of April, 1960.

My Commission Expires:

July 7, 1962

Mona L. Latier
Mona L. Latier - Notary Public

