

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-065-20501-00-00

LEASE NAME C. Dreiling #3

WELL NUMBER \_\_\_\_\_

SPOT LOCATION 1320' E of W.L.  
& 440'S of NL of NE/4  
SEC. 8 TWP. 10 RGE. 24 (R) or (S)

COUNTY Graham

Date Well Completed \_\_\_\_\_

Plugging Commenced 3/28/84

Plugging Completed 4/18/84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Don E. Pratt OIL Operation

ADDRESS P.O. Box 370, Hays, Ks. 67601

PHONE # (913) 625-3446 OPERATORS LICENSE NO. # 6114

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SMD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? \_\_\_\_\_

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? Hays

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4085'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	204'	none
				4 1/2"	4083'	685.29'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged off bottom with 4 sacks cement, sand to 3800' & 4 sacks cement. Shot pipe at 3025', 2348', & 685'. Pulled 22 joints of pipe. Plugged well with 3 hulls, 40 gal. 8.5/8 wiper plug, & 170 cement 50/50 poz 6% gel 3% c.c.

Plugging complete  
(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050  
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso. (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

RECEIVED  
STATE CORPORATION COMMISSION

APR 26 1984  
04-26-1984  
CONSERVATION DIVISION  
Wichita, Kansas

My Commission expires:

SUBSCRIBED AND SWORN TO before me this 24th day of April, 1984  
IRENE HOOVER  
State of Kansas  
My Comm. Exp. Aug. 15, 1985

Irene Hoover  
Notary Public



# DREILING OIL, INC.

Victoria, Kansas 67671

15-065-20501-00-00

WELL LOG  
Leon E. Pratt Oil Operations

Company P. O. Drawer 370  
Hays, Kansas 67601

Farm C. Dreiling No. 3

Total Depth 4085'

Comm. 11-13-71 Comp. 11-21-71

Contractor Dreiling Oil, Inc.

Victoria, Kansas 67671

Sec. 8 Twp. 10 Rng. 24  
1320' E. of W.L.  
Location 440'S. of N.L. of NE/4

County Graham

Elevation: 2487 K. B.

2484 D. F.

2482 G. R.

Casing Record  
204' - E 5/8"  
4083' - 4 1/2"

Cement Record  
165 sacks cement  
200 Sacks cement  
2% quick set and 10% Salt

Production:

### Figures Indicate Bottom of Formations

0'	135'	Top Soil Sand
135'	204'	Blue Shale
204'	330'	Shale
330'	1233'	Shale
1233'	1526'	Shale
1526'	1552'	Shale
1552'	1910'	Shale & Sand
1910'	2137'	Shale & Red Bed
2137'	2180'	Anhydrite
2180'	2290'	Shale & Lime Streaks
2290'	2544'	Shale
2544'	2790'	Shale
2790'	2995'	Shale & Lime
2995'	3220'	Shale
3220'	3475'	Shale
3475'	3642'	Shale & Lime
3642'	3765'	Lime & Shale
3765'	3847'	Lime & Shale
3847'	3876'	Lime
3876'	3953'	Lime
3953'	4022'	Lime
4022'	4085'	Lime
4085'	T.D.	

STATE OF KANSAS)  
)ss  
COUNTY OF ELLIS)

I, Leo F. Dreiling, of Dreiling Oil, Inc. upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from the C. Dreiling #3.

*Leo F. Dreiling*  
LEO F. DREILING

Subscribed and sworn to before me this 26th day of November, 1971.

*Joseph A. Hess*  
Joseph A. Hess, Notary Public

My commission expires: September 15, 1974.

RECEIVED  
STATE CORPORATION COMMISSION  
03-02-1984  
MAR 02 1984

CONSERVATION DIVISION  
Wichita, K.

