

15-065-21257-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Graham SEC. 8 TWP. 10S RGE. 24W E/W  
Location as in quarters or footage from lines:

SW NW NE


Lease Owner Don E. Pratt

Lease Name C. Drilling 6-8 Well No. \_\_\_\_\_

Office Address P.O. Box 370 Hays, Kansas 67601

Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_

Date Well Completed \_\_\_\_\_

Application for plugging filed \_\_\_\_\_

Plugging commenced 12-23-81

Plugging completed 1-7-82

Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom T.D. 4080'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	712'	none
				4-1/2"	4078'	1719'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

~~Plugged off bottom with sand to 3980' and set 4 sacks cement. Shot pipe @3081 and 3056'. Mud came in @2000'. Pumped mud out and pushed plug to 2800'. Shot casing @2777', 2577', 2400', 2081', 1995' and 1782'. Pulled a total of 41 joints of pipe. Plugged well with 4 sacks hulls, 12 sacks gel, 1 sack hulls, 70 sacks 50/50 pos, 4% gel, 3% cc, 12 sacks gel, 8-5/8" plug, 70 sacks 50/50 pos, 4% gel, 3% cc. Plugging Completed.~~

RECEIVED

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Kelso Casing Pulling

JAN 15 1982  
01-15-1982

STATE OF Kansas COUNTY OF Rice, ss. \_\_\_\_\_ CONSERVATION DIVISION

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of January, 19 82

My Commission expires: 


Irene Hoover  
Notary Public.

15-065-21257-00-00  
WELL LOG

COMPANY Don Pratt  
FARM C. DREILING NO. 6-8  
RIG. NO. 16  
TOTAL DEPTH 4080'  
COMM. 7-5-80 COMP. 7-12-80  
CONTRACTOR Murfin Drilling Company

SEC. 8 T. 10S R. 24W  
LOC. SW NW NE

COUNTY Graham  
KANSAS



CASINO  
20  
15  
12  
13

10 8-5/8" csg. set @ 712' -w/130 sx. of Quickset  
6  
5 4 1/2" csg. set @ 4078' w/175 sx. of Common, 2% CC, 8% salt.  
ELEVATION  
PRODUCTION  
FIGURES INDICATE BOTTOM OF FORMATIONS


115' Soil & Sand  
173' Shale  
570' Shale & Sand  
1420' Sand & Shale  
1702' Shale & Chirt  
1910' Sand  
2115' Shale & Red Beds  
2151' ANHYDRITE  
3250' Shale  
3495' Shale & Lime  
3920' Shale  
3978' Lime  
4080' Lime & Shale R T D

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1981  
12-10-1981  
CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS  
County of SEDGWICK

I, David L. Murfin, Drlg. Mgr. of the MURFIN DRILLING Company

upon oath state that the above and foregoing is a true and correct copy of the log of the C. DREILING #6-8 well.



David L. Murfin, Drlg. Mgr.

Subscribed and sworn to before me this 18th day of July 1980

My Commission Expires: May 21, 1983

Linda Lynch NOTARY PUBLIC