

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Berexco, Inc.

Address: PO Box 723 Hays, KS 67601

Phone: (785) 628-6101 Operator License #: 5363

Type of Well: oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 12-10-07 (Date)

by: Daryl Dipman (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

L-KC Depth to Top: 3921 Bottom: 3965 T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

20024-00-00 API Number: 15-065-19179-00-00 Lease Name: HANSEN Estate Fee Well Number: 4 Spot Location (QQQQ): SE-NE-SE 1650 3139 Feet from North South Section Line 330 646 Feet from East West Section Line Sec. 30 Twp. 8 S. R. 25 East West County: GRAHAM Date Well Completed: 3-19-67 Plugging Commenced: 12-10-07 Plugging Completed: 12-13-07

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include L-KC OIL with casing sizes 8-5/8" and 4-1/2 95#.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

TIH W/ OPENENDED TBG TO 3390' MIX 75 SKS COMMON W/ 200# HULLS AND 3% CC. PULL TBG TO 2306' MIX 75 SKS COMMON W/ 200# HULLS W/ 2%CC PULL TBG TO 1313' AND CIRC CMT W/ 100 SKS COMMON W/ 100# HULLS. TOH W/ TBG DUG CELLAR OUT, TIE ONTO 4-1/2 AND PMP ANOTHER 20 SKS COMMON DOWN 4-1/2 AND SQZ TO 300# AND SI TIE ONTO 8-5/8 AND PMP 30 SKS DOWN 8-5/8 AND SI AT 300#.

Name of Plugging Contractor: Berexco, Inc. License #: 5363

Address: PO Box 723 Hays, KS 67601


Name of Party Responsible for Plugging Fees: Mark Leiker w/ Berexco, Inc.

State of KS County, ELLIS, ss.

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Mark Leiker

(Address) PO Box 723 Hays, KS 67601



SUBSCRIBED and SWORN TO before me this 20th day of December, 2007. Shanna Miller, My Commission Expires: 9/19/09

Notary Public

RECEIVED KANSAS CORPORATION COMMISSION

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

DEC 26 2007

CONSERVATION DIVISION WICHITA, KS