

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Keith F. Walker Oil & Gas Company, L.L.C.

Address: 103 West Boyd Street- Norman, OK 73069

Phone: (405) 701-0676 Operator License #: 33392

Type of Well: D&A Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: (Date)

by: Steve Durrant (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (if needed attach another sheet)

None Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D. Depth to Top: Bottom: T.D.

API Number: 15-119-21216-00-00

Lease Name: Razor

Well Number: 3 #1

Spot Location (QQQQ): NE-NE-NE 330 Feet from North / South Section Line

330 Feet from East / West Section Line

Sec. 3 Twp. 32 S. R. 27 East West

County: Meade

Date Well Completed: 8/20/2008

Plugging Commenced: 8/22/2008

Plugging Completed: 8/22/2008

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows show 'None' for formation and casing sizes of 20", 13 3/8", and 8 5/8" with depths of 52', 672', and 1682' respectively.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Cement Plug at 1700' with 50 sx of Cement 60/40 Poz mix with 4% gel.

2nd Cement Plug at 400' with 50 sx of Cement 60/40 Poz with 4% gel.

3rd and Final Cement Plug at 60' with 20 sx of Cement 60/40 POZ with 4% gel.

Plug rat and mouse hole with 20 sx of Cement 60/40 POZ with 4% gel. All plugging done as per Steve Durrant.

Name of Plugging Contractor: Kenai Mid-Continent Inc J & L Cementing Service, LLC License #: 34000

Address: P.O. Box 848 Shattuck, OK 73853 580-938-2205 KCC PRT PER CP213 SEP 22 2008

Name of Party Responsible for Plugging Fees: Keith F. Walker Oil & Gas Company, L.L.C. CONSERVATION DIVISION WICHITA, KS

State of Oklahoma County, Cleveland, ss.

Sonya King, Engineer Tech of Keith F. Walker Oil & Gas Company, L.L.C. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Sonya King

(Address) 103 West Boyd Street- Norman, OK 73069



SUBSCRIBED and SWORN TO before me this 17 day of September, 20 08

Rebecca C. Casey My Commission Expires: 11.10.09 Notary Public