

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hess Oil Company

Address: P. O. Box 1009, McPherson, KS 67460

Phone: (620) 241-4640 Operator License #: 5663

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 1/29/08 (Date)

by: Deines (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 4350' Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-195-22,017-00-00

Lease Name: Caruso "D"

Well Number: 1

Spot Location (QQQQ): App - W2 - NE - SW

1865 Feet from North / South Section Line

3524 Feet from East / West Section Line

Sec. 22 Twp. 15 S. R. 25 East West

County: Trego

Date Well Completed: 6/27/89

Plugging Commenced: 7/25/08

Plugging Completed: 7/25/08

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|--------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| Surface | | 210' | 0' | 8-5/8" | 210' | none |
| Production | | 4349' | 0' | 5-1/2" | 4349' | none |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran in tubing to 4326' & pumped in 40 sx cement w/2 sx hulls. Pulled tubing to 4000' & pumped in 15 sx gel spacer. Pulled tubing to 1900' & pumped in 220 sx cement. Circ. to surface. Topped off 5-1/2" casing w/25 sx cement. Pumped in 115 sx cement between casings. Cement used - 400 sx 60/40 pozmix, 4% gel.

Name of Plugging Contractor: Hess Oil Company License #: 5663


Address: P. O. Box 1009, McPherson, KS 67460

Name of Party Responsible for Plugging Fees: Hess Oil Company

State of Kansas County, McPherson, ss.

Bryan Hess, President (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Bryan Hess
(Address) same

SUBSCRIBED and SWORN TO before me this 2nd day of September, 20 08

(Signature) Carol A. Nickel My Commission Expires: 6-1-09
Notary Public

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2008
CONSERVATION DIVISION
WICHITA, KS

Handwritten initials/signature



P. O. Box 466
Ness City, KS 67560
Off: 785-798-2300



Invoice

| | |
|-----------|-----------|
| DATE | INVOICE # |
| 7/25/2008 | 14807 |

| |
|---|
| BILL TO |
| Hess Oil Company PO Box 1009 McPherson, KS 67460-1009 |

- Acidizing
- Cement
- Tool Rental

| TERMS | Well No. | Lease | County | Contractor | Well Type | Well Category | Job Purpose | Operator |
|------------|-----------------------------------|--------|--------|-------------------|-----------|---------------|-------------|-----------|
| Net 30 | D #1 | Caruso | Trego | Fritzler Trucking | Oil | Workover | PTA | Wayne |
| PRICE REF. | DESCRIPTION | | | | QTY | UM | UNIT PRICE | AMOUNT |
| 575W | Mileage - 1 Way | | | | 25 | Miles | 6.00 | 150.00T |
| 576W-P | Pump Charge - PTA | | | | 1 | Job | 850.00 | 850.00T |
| 275 | Cotton Seed Hulls | | | | 2 | Sack(s) | 28.00 | 56.00T |
| 328 | Swift Light 60/40 Pozmix (4% Gel) | | | | 400 | Sacks | 10.50 | 4,200.00T |
| 279 | Bentonite Gel | | | | 15 | Sack(s) | 24.00 | 360.00T |
| 290 | D-Air | | | | 3 | Gallon(s) | 35.00 | 105.00T |
| 581W | Service Charge Cement | | | | 415 | Sacks | 1.90 | 788.50T |
| 583W | Drayage | | | | 438.5 | Ton Miles | 1.75 | 767.38T |
| | Subtotal | | | | | | | 7,276.88 |
| | Sales Tax Trego County | | | | | | 5.80% | 422.06 |

6133
AUG 5 PAID

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2008
CONSERVATION DIVISION
WICHITA, KS

We Appreciate Your Business!

Total

\$7,698.94

JOB LOG

SWIFT Services, Inc.

DATE 7-25-08 PAGE NO. 1

CUSTOMER Hess Oil Co. WELL NO. D-1 LEASE CARUSO JOB TYPE PTA TICKET NO. 14807

| CHART NO. | TIME | RATE (BPM) | VOLUME (BBLS/GAL) | PUMPS | | PRESSURE (PSI) | | DESCRIPTION OF OPERATION AND MATERIALS |
|-----------|------|------------|-------------------|-------|---|--------------------|--------|--|
| | | | | T | C | TUBING | CASING | |
| | 1200 | | | | | | | ON LOCATED |
| | | | | | | | | 2 3/8 x 5 1/2 5 1/2 = 4349 8 5/8 = 4349 - 60 OH = 210' |
| | 1440 | 4 | 10 1/2 | ✓ | | 900 | | PUMP 40 SKS CMT w/ 2 SKS HULLS = 4326' - CIRCULATION PULL TUBING TO 4000' |
| | 1515 | 4 | 51 | ✓ | | 1100 | | PUMP 15 SKS GEL SPACER TO 1900' PULL TUBING TO 1900' |
| | 1700 | 4 | 58 | ✓ | | 400 | | PUMP 220 SKS CMT - CIRCULATED CMT. TO SURFACE PULL TUBING OUT WELL |
| | 1830 | | 6 1/2 | ✓ | | | | TOP OFF 5 1/2 CSG 25 SKS CMT (STAY FULL) |
| | 1845 | 3 | 30 | ✓ | | 425 ^{MAX} | | PUMP 115 SKS CMT - BRASS HEAD |
| | 1900 | | | | | 225 | | SHUT IN BRASS HEAD WASH TRUCK |
| | 1930 | | | | | | | JOB COMPLETE |

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 04 2008
CONSERVATION DIVISION
WICHITA, KS

THANK YOU
WALKER, BOB, JEFF