

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Hess Oil Company

Address: P. O. Box 1009, McPherson, KS 67460

Phone: (620) 241-4640 Operator License #: 5663

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: _____ (Date)

by: _____ (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Cherokee Sand Depth to Top: 4280' Bottom: 4284' T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 135-24,340-00-00

Lease Name: Paula

Well Number: 1

Spot Location (QQQQ): App - N2 - N2 - SW
2350 Feet from North / South Section Line

1210 Feet from East / West Section Line

Sec. 5 Twp. 16 S. R. 21 East West

County: Ness

Date Well Completed: 3/2/05

Plugging Commenced: 8/5/08

Plugging Completed: 8/5/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface		209'	0'	8-5/8"	209'	none
Production		4360'	0'	5-1/2"	4360'	none

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pumped 235 sacks 60/40 pozmix, 4% gel as follows: 25 sx down 8-5/8", 40 sx down 5-1/2", 15 sx gel spacer, 170 sx cement, circ. to surface.

Name of Plugging Contractor: Hess Oil Company License #: 5663

Address: P. O. Box 1009, McPherson, KS 67460

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Hess Oil Company


SEP 04 2008

State of Kansas County, McPherson, ss.

CONSERVATION DIVISION
WICHITA, KS

Bryan Hess, President

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) Bryan Hess
(Address) same

SUBSCRIBED and SWORN TO before me this 3rd day of September, 20 08

Carol A. Nickel My Commission Expires: 6-1-09
Notary Public

[Handwritten initials]



P. O. Box 466
 Ness City, KS 67560
 Off: 785-798-2300



API 15-135-24340-00-00

Invoice

DATE	INVOICE #
8/5/2008	14818

BILL TO
Hess Oil Company PO Box 1009 McPherson, KS 67460-1009

- Acidizing
- Cement
- Tool Rental

TERMS	Well No.	Lease	County	Contractor	Well Type	Well Category	Job Purpose	Operator
Net 30	#1	Paula	Ness		Oil	Workover	PTA	Wayne
PRICE REF.	DESCRIPTION				QTY	UM	UNIT PRICE	AMOUNT
575W	Mileage - 1 Way				30	Miles	7.00	210.00T
576W-P	Pump Charge - PTA				1	Job	850.00	850.00T
275	Cotton Seed Hulls				4	Sack(s)	28.00	112.00T
328	Swift Light 60/40 Pozmix (4% Gel)				235	Sacks	10.50	2,467.50T
279	Bentonite Gel				15	Sack(s)	24.00	360.00T
290	D-Air				2	Gallon(s)	35.00	70.00T
581W	Service Charge Cement				250	Sacks	1.90	475.00T
583W	Drayage				318.975	Ton Miles	1.75	558.21T
	Subtotal							5,102.71
	Sales Tax Ness County						5.30%	270.44
We Appreciate Your Business!							Total	\$5,373.15

6204
 AUG 13 PAID

JOB LOG

SWIFT Services, Inc.

DATE 8-5-08 PAGE NO. 1

CUSTOMER Hess Oil Co. WELL NO. # 1 LEASE PAULA JOB TYPE PTA TICKET NO. 14818

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL/GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1300							ON LOCATION
								8 5/8" = 209'
								5 1/2" = 4360'
								DU = 1750 ±
								PERF = 4280-84
	1340	1 1/2	6 1/2		✓		500	PUMP DOWN BRASS HEAD - 25 SKS OMT
								PUMP DOWN 5 1/2" CASING
	1415	5	10 1/2		✓		0	40 SKS CEMENT w/ 4 SKS HULLS
		5	50		✓		0	15 SKS GEL
		1 3/4	45		✓		1150 ^{MAX}	170 SKS CEMENT TO SURFACE
							0	SHUT IN
								WASH TRUCK
	1500							JOB COMPLETE
								THANK YOU
								WALTER BEATT, JR