

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Lease Operator: Anadarko Petroleum Corporation
Address: PO Box 1330 Houston, TX 77251-1330
Phone: (832) 636-8380 Operator License #: 4549
Type of Well: Gas Docket #:
The plugging proposal was approved on: Unknown (Date)
by: Ken Jehlik (KCC District Agent's Name)
Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No
Producing Formation(s): List All (If needed attach another sheet)
Krider Depth to Top: 2062 Bottom: 2088 T.D. 2130'

API Number: 15- 129-21156 -00 -00
Lease Name: USA AH
Well Number: 1
Spot Location (QQQQ): nw NE - NW - SE - SE
1250 Feet from [] North / [X] South Section Line
1000 Feet from [X] East / [] West Section Line
Sec. 7 Twp. 34 S. R. 41 [] East [X] West
County: Morton
Date Well Completed: 01/25/1993
Plugging Commenced: 08/19/2008
Plugging Completed: 08/21/2008

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out). Rows show casing data for 0-629', 0-2065', and 2030'-2130'.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from (bottom), to (top) for each plug set.

Mixed 300 lbs hulls & 25 sks cmt & set plug from 2062' to 1862'. Circ hole w/mud & set 25 sks cmt plug from 1450' to 1250'. Worked pipe. Could not cut/pull 5.5" csg. Set 50 sks cmt plug from 700' to 300'. Mix 5 sk cmt plug & spot down annulus from 30' - 0'. Mixed 8 sk plg & plugged 5.5" csg from 60' to surface. Cut off 8-5/8 & 5.5" csg. Capped 8-5/8" 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151
Address: Rt. 1 Box 49BA Tyrone, OK 73951-9731


Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation
State of Texas County, Montgomery, ss.

Diana Smart Staff Regulatory Analyst (Employee of Operator) or (Operator) on above-described well, duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart
(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 5th day of September, 20 08

Bertha Nefe Notary Public My Commission Expires: 12-27-09



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED KANSAS CORPORATION COMMISSION SEP 09 2008

CONSERVATION DIVISION

Handwritten initials 'PK' in the bottom right corner.