

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

WELL PLUGGING RECORD

K.A.R. 82-3-117

Lease Operator: Anadarko Petroleum Corporation

Address: PO Box 1330 Houston, TX 77251-1330

Phone: (832) 636-8380 Operator License #: 4549

Type of Well: Gas Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: Unknown (Date)

by: Richard Lacey (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Topeka Depth to Top: 2922 Bottom: 2978 T.D. 3170

Waubunsee Depth to Top: 2684 Bottom: 2725 T.D.

Depth to Top: Bottom: T.D.

API Number: 15- 129-50005 -00-02

Lease Name: Mayberry

Well Number: 1-4

Spot Location (QQQQ): C - SE

1320 Feet from North / South Section Line

1320 Feet from East / West Section Line

Sec. 4 Twp. 34 S. R. 43 East West

County: Morton

Date Well Completed: 12/19/1956

Plugging Commenced: 08/29/2008

Plugging Completed: 09/02/2008

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put in, Pulled out)

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Set 4.5" CIBP @ 2565' & spot 2 sks cmt on top of CIBP. Shot 4.5" csg loose @ 831' and pull to 700'. Mix 40 sks cmt & spot plug from 700' to 500'. Pull csg to 350'. Mix 20 sks cmt and spot plug from 350' to 250'. Pull csg to 40'. Mix 8 sks cmt & spot plug from 40' to 0'. Cut off & cap 7" csg 3' below GL.

Name of Plugging Contractor: Sargent and Horton Plugging, Inc. License #: 31151

Address: Rt 1 Box 49BA Tyrone, OK 73951-9731

Name of Party Responsible for Plugging Fees: Anadarko Petroleum Corporation

State of Texas County, Montgomery, ss.

Diana Smart (Employee of Operator) or (Operator) on above-described well, being first duly


sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) Diana Smart

(Address) PO Box 1330 Houston, TX 77251-1330

SUBSCRIBED and SWORN TO before me this 8th day of September 2008

(Signature) Pamela C Frye My Commission Expires: 3/17/09



RECEIVED KANSAS CORPORATION COMMISSION

SEP 09 2008

CONSERVATION DIVISION WICHITA, KS

PKA