

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Paul Bowman Oil Trust  
Address: 801 Codell Road Codell, Kansas 67663  
Phone: (785) 434-2286 M-F Operator License #: 33723  
Type of Well: SWD Docket #: D-20,141  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: September 4, 2008 (Date)  
by: Pat Staab KCC District #4-Hays, Kansas (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Perforations Depth to Top: 1250' Bottom: 1300' T.D. 3851'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. PB 1325'  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 163-21121-0001  
Lease Name: Largent-Dick  
Well Number: #1 SWD  
Spot Location (QQQQ): \_\_\_\_\_ - E/2 - SW - NE,  
3300' Feet from  North /  South Section Line  
1650' Feet from  East /  West Section Line  
Sec. 29 Twp. 10 S. R. 19  East  West  
County: Rooks County, Kansas  
Date Well Completed: March 18, 1981  
Plugging Commenced: September 4, 2008  
Plugging Completed: September 4, 2008

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records |         | Casing Record (Surface Conductor & Production) |       |        |        |            |
|---------------------------|---------|--|-------|--------|--------|------------|
| Formation                 | Content | From   | To    | Size   | Put In | Pulled Out |
| Perforations 1250'-1300'  |         | 0 (Surface)                                    | 241'  | 8 5/8" | 241'   | 0'         |
|                           |         | 0 (Surface)                                    | 3773' | 4 1/2" | 3773'  | 0'         |
|                           |         |  |       |        |        |            |
|                           |         |  |       |        |        |            |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

1st Plug @1125', mixed 175 sxs & 500# Hulls, took on vacuum, mixed 60 sxs 250# Hulls, Cement Circulated, Tied onto Casing and mixed 10 sxs, Shut in, pressure of 250 PSI, Tied onto 8 5/8", mixed 5 sxs, Shut in at 100 PSI.  
Used 235 sxs 60-40, 4% Gel, and 750# Hulls. (See Copy of Cementing Ticket attached)

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Allied Cementing Company, LLC License #: 99996 **SEP 08 2008**  
Address: 24 S. Lincoln Russell, Kansas 67665 *KCC* CONSERVATION DIVISION  
Name of Party Responsible for Plugging Fees: Paul Bowman Oil Trust WICHITA, KS


State of Kansas County, Rooks, ss.  
Connie Jo Austin - Agent for Paul Bowman Oil Trust (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Connie Jo Austin Agent for Paul Bowman Oil Trust

(Address) 801 Codell Road Codell, Kansas 67663

My Appt. Expires 2-24-07 SUBSCRIBED and SWORN TO before me this 5<sup>th</sup> day of September, 2008

*Jackie J. Langholz*  
Notary Public My Commission Expires: 2-24-2009



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

