

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: American Warroir inc.

Address: P.O. Box 399 Garden City Ks. 67846

Phone: (620) 272-1023 Operator License #: 4058

Type of Well: ENHR Docket #: E-26,889  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 8/3/08 (Date)

by: Pat Bedore (KCC District Agent's Name)

Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Depth to Top:	Bottom:	T.D.

API Number: 15-167-20336-00-01

Lease Name: Hall

Well Number: #11

Spot Location (QQQQ): 6 E/2 SE SE KCC  
600' 628' Feet from ☐ North / ☒ South Section Line PIC  
330' 429' Feet from ☒ East / ☐ West Section Line per OPS

Sec. 36 Twp. 14S S. R. 15W ☐ East ☒ West

County: Russell

Date Well Completed: 5/21/94

Plugging Commenced: 8/4/08

Plugging Completed: 8/4/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		804'	surface	85/8	804'	0
		3207'	surface	51/2	3207'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Run tbg to 2800'. Swift hooked up to tbg, mixed and pumped 10sx gel, 50sx 60/40 pos 4% gel with 200# of hulls. Pulled tbg to 825' Swift hooked up to tbg, Mixed and pumped 125sx 60/40 pos 4% gel. Cement circulated to surface. Pulled tbg. Topped 51/2 off. Swift hooked up to annulus, Pressured to 500# held. Cut casing off 6' below surface and back filled.

Name of Plugging Contractor: Expresswell Service & Supply Inc License #: 32382 RECEIVED  
Address: P.O. Box 466 Nesscity Ks. 67560 KANSAS CORPORATION COMMISSION  
Name of Party Responsible for Plugging Fees: American Warrior Inc. SEP 04 2008  
State of Kansas County, Finney, ss. CONSERVATION DIVISION  
Jody Smith WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature)

(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 2 day of September, 20 08

Erica Kuhlmeier  
Notary Public

My Commission Expires: 09/12/09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202