

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Range Oil Company, Inc.
Address: 125 N. Market, Suite 1120 Wichita, KS 67202
Phone: (316) 265-6231 Operator License #: 5120
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-11-08 (Date)
by: Greg Eves (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Viola Depth to Top: 2145' Bottom: _____ T.D. 2230'

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15 - 017-20,896 - 00 - 00
Lease Name: Panther Ranch
Well Number: 2
Spot Location (QQQQ): Approx. - W/2 - NW
1475 Feet from North / South Section Line
510 Feet from East / West Section Line
Sec. 29 Twp. 19 S. R. 6 East West
County: Chase
Date Well Completed: 6-15-07
Plugging Commenced: 8-22-08
Plugging Completed: 8-25-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	221'	none
				4 1/2	2229'	300'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Filled bottom of casing with sand up to 2105' and bailed four sacks cement on top. Dug cellar, unpacked casing head and pulled slips. Ripped casing at 300' and pipe came free. Left casing at 300' and pumped 110 sacks of cement to surface (Concrete Products, Inc. ticket #44284). Pulled remaining casing and welded cap on top of 8 5/8" casing.

Name of Plugging Contractor: Sunflower Well Service, Inc. License #: 30280
Address: P. O. Box 341 - Canton, KS 67428
Name of Party Responsible for Plugging Fees: Range Oil Company, Inc.
State of Kansas County, Sedgwick, ss. _____

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 10 2008
CONSERVATION DIVISION
WICHITA, KS

John M. Washburn (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John M. Washburn
(Address) 125 N. Market, Suite 1120 Wichita, KS 67202



SUBSCRIBED and SWORN TO before me this 9th day of September, 2008
Peggy L. Sailor My Commission Expires: 12-08-11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202