

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Range Oil Company, Inc.
Address: 125 N. Market, Suite 1120 Wichita, KS 67202
Phone: (316) 265-6231 Operator License #: 5120
Type of Well: D&A Oil / KCCPKT REC CP 2/3 Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8-11-08 (Date)
by: Greg Eves (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. 2271'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-017-20,894-00-00
Lease Name: Panther Ranch
Well Number: 1
Spot Location (QQQQ): _____ - NE - SE - NE
1650 Feet from North / South Section Line
330 Feet from East / West Section Line
Sec. 30 Twp. 19 S. R. 6 East West
County: Chase
Date Well Completed: 3-1-07
Plugging Commenced: 8-21-08
Plugging Completed: 8-21-08

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface Conductor & Production) | | | | |
|---------------------------|---------|--|----|-------|--------|------------|
| Formation | Content | From | To | Size | Put In | Pulled Out |
| | | | | 8 5/8 | 240' | none |
| | | | | 4 1/2 | 2246' | 800' |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Filled bottom of casing with sand up to 2135' and bailed four sacks cement on top. Dug cellar, unpacked casing head and pulled slips. Ripped casing at 800' and pipe came free. Pulled casing up to 300' and pumped 110 sacks of cement to surface (Concrete Products, Inc. ticket #44276). Pulled remaining casing and welded cap on top of 8 5/8" casing.

Name of Plugging Contractor: Sunflower Well Service, Inc. License #: 30280
Address: P. O. Box 341 - Canton, KS 67428 RECEIVED KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Range Oil Company, Inc. SEP 10 2008

State of Kansas County, Sedgwick, ss. John M. Washburn (Employee of Operator) or (Operator) on above-described well, being first duty

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

PEGGY L. SAILOR
Notary Public - State of Kansas
My Appt. Expires December 8, 2011

(Signature) John M. Washburn
(Address) 125 N. Market, Suite 1120 Wichita, KS 67202

SUBSCRIBED and SWORN TO before me this 9th day of September, 20 08
Peggy L. Sailor My Commission Expires: 12-8-11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT