

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Range Oil Company, Inc.  
Address: 125 N. Market, Suite 1120 Wichita, KS 67202  
Phone: (316) 265-6231 Operator License #: 5120  
Type of Well: Gas Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: 8-11-08 (Date)  
by: Greg Eves (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
Mississippian Depth to Top: 2824' Bottom: \_\_\_\_\_ T.D. 2851'  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-115-21,323<sup>3</sup>-00-00  
Lease Name: Becker E  
Well Number: 2  
Spot Location (QQQQ): Approx - SW - SE - NW  
2155 Feet from  North /  South Section Line  
1500 Feet from  East /  West Section Line  
Sec. 10 Twp. 19 S. R. 1  East  West  
County: Marion  
Date Well Completed: 1-14-05  
Plugging Commenced: 8-18-08  
Plugging Completed: 8-19-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	264'	none
				4 1/2	2851'	1680'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.  
Filled bottom of casing with sand up to 2775' and bailed four sacks cement on top. Dug cellar, unpacked casing head and pulled slips. Ripped casing at 1680' and pipe came free. Pulled casing up to 315' and pumped 132 sacks of cement to surface (Concrete Products, Inc. ticket #44256). Pulled remaining casing and welded cap on top of 8 5/8" casing.

Name of Plugging Contractor: Sunflower Well Service, Inc. License #: 30280 **RECEIVED**  
Address: P. O. Box 341 - Canton, KS 67428 **SEP 10 2008**  
Name of Party Responsible for Plugging Fees: Range Oil Company, Inc. **CONSERVATION DIVISION**  
State of Kansas County, Sedgwick, ss. **WICHITA, KS**

John M. Washburn (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) John M. Washburn  
(Address) 125 N. Market, Suite 1120 Wichita, KS 67202

**PEGGY L. SAILOR**  
Notary Public - State of Kansas  
My Appt. Expires December 8, 2011

SUBSCRIBED and SWORN TO before me this 9th day of September, 2008  
Peggy L. Sailor My Commission Expires: 12-8-11  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten signature]*