

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: Ritchie Exploration, Inc. Address: P. O. Box 783188 Phone: (316) 691-9500 Operator License #: 4767 Type of Well: Oil Docket #: The plugging proposal was approved on: 08/20/2008 by: Pat Bedore Is ACO-1 filed? Yes No If not, is well log attached? Yes No Producing Formation(s): Lansing-KC Depth to Top: 3559' Bottom: 3710' T.D. 3980' Toronto Depth to Top: 3543' Bottom: 3546' T.D. 3980'

API Number: 15-137-20284-00-00 Lease Name: Wyrill C KCC PKT per CP2/3 Well Number: #1 Spot Location (QQQQ): - SW - SW - SW 330 Feet from North / South Section Line 330 Feet from East / West Section Line Sec. 34 Twp. 5 S. R. 23 East West County: Norton Date Well Completed: 05/05/1983 Plugging Commenced: 08/19/2008 Plugging Completed: 08/20/2008

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out). Rows include Lansing-KC, Toronto, and CIBP.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Perforated 4 1/2" casing at 2050' and at 1270'. Ran 2 3/8" tubing to 2330'. Pumped 100 sx 60/40 Pozmix w/4% gel + 300# hulls. Pulled tubing up to 1200'. Pumped 100 sx 60/40 Pozmix w/4% gel + 200# hulls. Circulated cement to surface. Pulled tubing out of hole. Pumped 15 sx 60/40 Pozmix w/4% gel down casing. Pumped 15 sx 60/40 Pozmix w/4% gel down 8 5/8" surface casing. Shut-in at 150#. Plugging complete on 08/20/2008 witnessed and approved by Pat Bedore with the KCC


Name of Plugging Contractor: Allied Cementing License #: 66426 Address: P. O. Box 31 Russell, KS 67665 KCC PKT per CP2/3

Name of Party Responsible for Plugging Fees: Ritchie Exploration, Inc. State of Kansas County, Norton, ss.

John Niernberger - employee of Ritchie Exploration, Inc. (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) (Address) P. O. Box 783188 Wichita, KS 67278-3188

SUBSCRIBED and SWORN TO before me this 17th day of September 20 08 My Commission Expires: 5/7/2012



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED KANSAS CORPORATION COMMISSION SEP 18 2008

Handwritten initials/signature