

Notice: Fill out COMPLETELY  
and return to Conservation Division  
at the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

KCC PRT 201  
CP 2/3

Lease Operator: Southern Star Central Gas Pipeline

Address: 4700 Ky. Hwy. 56 West, P.O. Box 20010 Owensboro, Ky. 42304

Phone: (270) 852-4489 Operator License #: 33097

Type of Well: Gas Storage Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 2/15/08 (Date)

by: Clayton Titel (KCC District Agent's Name)

Is ACO-1 filed? ☐ Yes ☒ No If not, is well log attached? ☐ Yes ☒ No

Producing Formation(s): List All (If needed attach another sheet)

Colony Ss. Depth to Top: 920' Bottom: 929' T.D. 929'

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 207-19426-00-01

Lease Name: Piqua Storage Field Coas storage

Well Number: 10

Spot Location (QQQQ): \_\_\_\_\_ - \_\_\_\_\_ - SW - NE

3300' Feet from ☐ North / ☒ South Section Line

2004' Feet from ☒ East / ☐ West Section Line

Sec. 3 Twp. 25 S. R. 17 ☒ East ☐ West

County: Woodson

Date Well Completed: 08/04/23

Plugging Commenced: 07/08/08

Plugging Completed: 07/16/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Colony Ss.	gas	0'	16'	10"		
		0'	900'	6 5/8"		

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Casing Perforated from 849' to 850' and 867' to 868' to get a better plug job. Ran 2 3/8" tubing to TD and cemented until cement circulated to surface. Tripped out of hole and well was topped of with cement and then well was squeezed from the surface and shut in. 158 sks total.

Casing cut 4' below surfaced and capped.

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Hurricane Services, Inc. License #: 34059

Address: PO Box 782228, Wichita, KS 67278

SEP 16 2008

Name of Party Responsible for Plugging Fees: Southern Star Central Gas Pipeline

CONSERVATION DIVISION  
WICHITA, KS

State of Kentucky County, Daviess, ss.

Charles C. McConnell

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above described well is as filed, and the same are true and correct, so help me God.

(Signature) Charles C. McConnell

(Address) SSCGP P.O. Box 20010

SUBSCRIBED and SWORN TO before me this 15<sup>th</sup> day of September, 20 08

Karen J. Hollman  
Notary Public

My Commission Expires: 8-26-2011

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202