

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: PINTAIL PETROLEUM, LTD.
Address: 225 N. MARKET, SUITE 300, WICHITA, KS 67202
Phone: (316) 263-2243 Operator License #: 5086
Type of Well: GAS Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 8/25/2008 (Date)
by: JEFF KOCK (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
MISSISSIPPI Depth to Top: 4392 Bottom: 4402 T.D. 5085

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-077-21446 ← 00-00
Lease Name: WOLFF
Well Number: 1
Spot Location (QQQQ): C - NW - _____
1320 Feet from North / South Section Line
1320 Feet from East / West Section Line
Sec. 24 Twp. 33 S. R. 6 East West
County: HARPER
Date Well Completed: 1-21-03
Plugging Commenced: 8-26-08
Plugging Completed: 8-28-08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
MISSISSIPPI	GAS			8-5/8"	285'	NONE
				4-1/2" 7.875	5082	3420

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pulled 52 jts tubing up to rods, changed over for rods, pulled rods, pulled rest of tubing, changed over for casing, tied on to 4 1/2" casing, pumped 30 sx, 200# hulls, displaced down to 4000', max pressure 200 psi, shut in 150 psi, dug cellar, unpacked casing head, set floor, pulled slips, cut surface off 4' below ground, had 3-" stretch, ripped casing at 3610', worked pipe, ripped casing at 3420', pipe came free, pulled casing up to 1050', pumped 35 sacks, 100# hulls, pulled to 700' pumped 35 sacks, 100# hulls, pulled to 320', circulated with 100 sacks to surface, pulled rest of casing.

Name of Plugging Contractor: QUALITY WELL SERVICE License #: 31925
Address: 190 US HIGHWAY 56, ELLINWOOD, KS 67526

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: PINTAIL PETROLEUM, LTD.

SEP 12 2008

State of KANSAS County, SEDGWICK, ss.

CONSERVATION DIVISION
WICHITA, KS

BETH A. ISERN (Employee of Operator) or (Operator) on above-described well, being first duly

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Beth A. Isern


(Address) 225 N. MARKET, SUITE 300, WICHITA, KS 67202

SUBSCRIBED and SWORN TO before me this 11 day of SEPTEMBER, 20 08

Susan Utterback
Notary Public

My Commission Expires: 9/18/2010

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



JKK