

**KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION**
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
**This Form must be Typed
Form must be Signed
All blanks must be Filled**

API # 15 - 141-01.000-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date _____.

Well Operator: John Roy Evans Oil Company, LLC KCC License #: 7030
(Owner / Company Name) (Operator's)

Address: P.O. Box 385 City: Claffin

State: Kansas Zip Code: 67525 Contact Phone: (620) 793 - 2026

Lease: Finnesy Well #: 2 "OWWO" Sec. 2 Twp. 10 S. R. 15 East West

S/2-N/2 - SE - SE - NE Spot Location / QQQQ County: Osborne

2970 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

330 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 8 5/8 Set at: 206 Cemented with: unknown Sacks

Production Casing Size: 4 1/2 Set at: 3768 Cemented with: 250 sx 50/50 pozmix Sacks

List (ALL) Perforations and Bridgeplug Sets: 3084-86; 3123-25; 3141-45; 3188-90; 3329-31; 3358-62; 3411-13

Elevation: 1904 (G.L. / K.B.) T.D.: 3769 PBTD: 3745 Anhydrite Depth: 1114-1148
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): Perforate 2 holes base of salt section around 1500'; Perforate 2 holes base of anhydrite section around 1150'; Perforate 2 holes freshwater base around 600'. Run tubing to 3000' and pump 150 sx cement. Pull tubing to 1500' and pump 80-100 sx cement. Pull tubing to 700' and circulate cement to surface as per KCC instruction.

**RECEIVED
KANSAS CORPORATION COMMISSION**

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

SEP 25 2008

If not explain why? _____

**CONSERVATION DIVISION
WICHITA, KS**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Gary Kirmer

Phone: (620) 793- - 2026


Address: P.O. Box 536 City / State: Claffin, KS 67525

Plugging Contractor: Express Well Service & Supply, Inc. KCC License #: 6426
(Company Name) (Contractor's)

Address: P.O. Box 19, Victoria, KS. 67671-0019 Phone: (785) 735 - 9405

Proposed Date and Hour of Plugging (if known?): Sept/Oct 2008

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent.

Date: 9/23/08 Authorized Operator / Agent:  (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 4
OK



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

JOHN ROY EVANS OIL COMPANY LLC
405 FOURTH ST
BOX 385
CLAFLIN, KS 67525

October 02, 2008

Re: FINNESY #2 OWWO
API 15-141-01000-00-01
2-10S-15W, 2970 FSL 330 FEL
OSBORNE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after March 31, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550