

**Notice:** Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117**

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Bullseye Petroleum, Inc.  
 Address: 15820 Plymouth Road Wichita, Kansas 67230  
 Phone: (316) 733-5280 Operator License #: 9913  
 Type of Well: Oil Docket #: \_\_\_\_\_  
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
 The plugging proposal was approved on: \_\_\_\_\_ (Date)  
 by: Steve Van Gieson (KCC District Agent's Name)  
 Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
 Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-077-21544-00-00  
 Lease Name: Nordhus-Drouhard  
 Well Number: 2  
 Spot Location (QQQQ): W2 - NW - SE - SW  
1010 Feet from  North /  South Section Line  
1510 Feet from  East /  West Section Line  
 Sec. 34 Twp. 31 S. R. 5  East  West  
 County: Harper  
 Date Well Completed: \_\_\_\_\_  
 Plugging Commenced: 8-26-08  
 Plugging Completed: 8-29-08

KCC CP-4  
Per CP-4

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	222	None
				5-1/2"	4661	3588

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Plugged off bottom with sand to 4570' and 5 sxs. cement. Cut casing loose @3588', pulled up to 1400', pumped 35 sxs cement, pulled up to 900', pumped 35 sxs., pulled up to 270' and circulated 80 sxs. cement to surface. 60/40 pos, 4% gel. Plugging Complete.

RECEIVED  
KANSAS CORPORATION COMMISSION  
**SEP 24 2008**  
CONSERVATION DIVISION  
WICHITA, KS

Name of Plugging Contractor: Mike's Testing & Saivage, inc. License #: 31529  
 Address: P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: Bullseye Petroleum, Inc.  
 State of Kansas County, Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
 (Address) P.O. Box 467 Chase, Kansas 67524

SUBSCRIBED and SWORN TO before me this 22nd. day of September 20 08

[Signature] My Commission Expires: \_\_\_\_\_  
 Notary Public  
 NOTARY PUBLIC - State of Kansas  
**IRENE HERZBERG**  
 My Appt. Exp. 8-24-09

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Signature]