

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warroir inc.
Address: P.O. Box 399 Garden City Ks. 67846
Phone: (620) 272-1023 Operator License #: 4058
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/22/08 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
KC Depth to Top: 3175' Bottom: 3254' T.D. 3305'
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-009-15320-00-00
Lease Name: Kraft-Prusa Unit
Well Number: 6-5
Spot Location (QQQQ): C - W/2 - SW - SE
660' Feet from North / South Section Line
2310' Feet from East / West Section Line
Sec. 12 Twp. 17 S. R. 11 East West
County: Barton
Date Well Completed: 5/19/41
Plugging Commenced: 9/23/08
Plugging Completed: 9/23/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
KC	oil	surface	278'	85/8	278'	0
		surface	3305'	51/2	3305'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1410', 675', 330', 2spf. Ran tbg to 3110'. Swift hooked up to tbg, Mixed and puped 50sx 60/40 poss 4% gelw/ 100# hulls. Pulled tbg to 2770'.
Swift hooked up to tbg, mixed and pumped 13sx Gel. Pulled tbg to 1420'. Swift hooked up to tbg, Mixed and pumped 150
sx 60/40 pos 4% gelw/ 200# hulls. Pulled tbg. Swift hooked up to 51/2, Mixed and pumped 50sx 60/40 poss 4% gel. Swift hooked up to 85/8,
Mixed and pumped 20 sx 60/40 poss 4% gel.

Name of Plugging Contractor: Express Well Service + Supply Inc License #: 32382 6426
Address: P.O. Box 466 Nesscity Ks. 67560
Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.
Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) P.O. Box 399 Garden City Ks. 67846

SUBSCRIBED and SWORN TO before me this 24 day of September, 2008
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCCPKT
PER CP 2/3

[Handwritten mark]