

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warroir inc.
Address: P.O. Box 399 Garden City Ks. 67846
Phone: (620) 272-1023 Operator License #: 4058
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9/2/08 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3403' Bottom: 3409 T.D. 3409
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: ⁰⁰⁹ 15-099-03820-00-00
Lease Name: Kraft-Prusa Unit KCCPKT DETCP2/3
Well Number: 2-6
Spot Location (QQQQ): C - NE - NE - NE
4950' Feet from North / South Section Line
330' Feet from East / West Section Line
Sec. 12 Twp. 17 S. R. 11 East West
County: Barton
Date Well Completed: 9/15/50
Plugging Commenced: 9/24/08
Plugging Completed: 9/24/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Arbuckle	oil	surface	260'	85/8	260'	0
		surface	3403'	51/2	3403'	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1415', 700', 350'. Ran tbg to 2403'. Swift hooked up to tbg, Mixed and pumped 75sx 60/40 poss 4% gel. Pulled tbg to 1900'. Swift hooked up to tbg, Mixed and pumped 100sx 60/40 pos 4% gel w/ 100# hulls. Pulled tbg to 800'. Swift hooked up to tbg, Mixed and pumped 140sx 60/40 poss 4% gel. Circulated cement. Pulled tbg. Topped 51/2 off with 10sx 60/40 pos 4% gel.

Express Well Services & Supply Inc

KCCPKT DETCP2/3

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: Swift Services Inc. License #: 32382
Address: P.O. Box 466 Nesscity Ks. 67560
0426 **SEP 26 2008**

Name of Party Responsible for Plugging Fees: American Warrior Inc.
State of Kansas County, Finney, ss.

CONSERVATION DIVISION
WICHITA, KS

Jody Smith (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) P.O. Box 399 Garden City Ks. 67846

ERICA KUHLMIEER
Notary Public - State of Kansas
My Appt. Expires 09-12-09

SUBSCRIBED and SWORN TO before me this 25 day of September, 2008
[Signature] My Commission Expires: 09-12-09
Notary Public

[Handwritten mark]