

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Quest Cherokee, LLC  
Address: 211 W. 14th Street Chanute, KS 66720  
Phone: (620) 431-9500 Operator License #: 33344  
Type of Well: unknown Oil Docket #: KCC PRT per CP2/3  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)  
The plugging proposal was approved on: 3/12/08 (Date)  
by: \_\_\_\_\_ (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_  
Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-133-01585-00-00  
Lease Name: Smith, Eddie 22-27-19-OW1  
Well Number: \_\_\_\_\_  
Spot Location (QQQQ): SW - \_\_\_\_\_ - \_\_\_\_\_  
1945 2066 Feet from  North /  South Section Line CP2/3  
228 5146 Feet from  East /  West Section Line KCC  
Sec. 22 Twp. 27 S. R. 19  East  West GPS.  
County: Neosho  
Date Well Completed: unknown  
Plugging Commenced: 3/12/08  
Plugging Completed: 3/12/08

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		unknown	unknown	unknown	unknown	none
		733'	surface	2-3/8"	733	733

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

This is an old well bore that we were unaware. We do not have any information on this well  
rig crew ran 2-3/8" tubing down hole for the wash job. Vac arrived on location to pull water out of the earth pit while washing the tubing down hole. Cement crew rigged up on location and finished washing down the last two joints of tubing.  
After reaching T.D. w/ tubing the cement crew switched to cement & broke circulation w/ good cement. Rig crew pulled 11 joints of tubing out of the hole and cement crew hooked  
back on to the tubing and circulated cement to surface again. Then the rig crew pulled the remaining 11 joints of tubing out of the hole and the cement crew topped off the well with cement. And rigged down off location. Used 140 aks of cement. Well plugged

Name of Plugging Contractor: Quest Cherokee Oilfield Service, LLC License #: 33344  
Address: 211 W. 14th Street, Chanute, KS 66720

RECEIVED  
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Quest Cherokee, LLC  
State of Kansas County, Neosho, ss.

SEP 24 2008

CONSERVATION DIVISION  
WICHITA, KS

Quest Cherokee, LLC (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Eddie R. Smith  
(Address) 211 W. 14th Street, Chanute, KS 66720  
TERRA KLAUMAN  
Notary Public - State of Kansas  
My Appt. Expires 8-4-2010

SUBSCRIBED and SWORN TO before me this 22nd day of September, 20 08  
Terra Klauman My Commission Expires: 8-4-2010  
Notary Public