

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Quest Cherokee, LLC
 Address: 211 W. 14th Street Chanute, KS 66720
 Phone: (620) 431-9500 Operator License #: 33344
 Type of Well: unknown Oil KCC PPT Per CP2/3 Docket #: _____
 (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
 The plugging proposal was approved on: 7/18/08 (Date)
 by: _____ (KCC District Agent's Name)
 Is ACO-1 filed? Yes No If not, is well log attached? Yes No
 Producing Formation(s): List All (If needed attach another sheet)
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____
 _____ Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-133-01581-00-00
 Lease Name: Taylor, Maryetta 26-28-18-OW1
 Well Number: _____
 Spot Location (QQQQ): SC NW 5 enw
1781 3503 Feet from North / South Section Line
2085 3402 Feet from East / West Section Line
 Sec. 26 Twp. 28 S. R. 18 East West
 County: Neosho
 Date Well Completed: unknown
 Plugging Commenced: 7/18/08
 Plugging Completed: 7/18/08

KCC PPT Per CP2/3

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
		unknown	unknown	unknown	unknown	none
		700	surface	2-3/8"	700	700

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

This is an old well bore that we were unaware. We do not have any information on this well
 rigged up on location to begin drilling on an old abandoned well down to T.D. in preparation for plugging. Rig ran 2-3/8" tubing/ drill collars down hole to drill. Rig crew ran down to 355' and started drilling. Started drilling on what was believed to be a hedge post. After continuous drilling, the crew finally reached 700' and couldn't make any more progress. Cement crew then tied on to the tubing and started pumping 14# cement. After bringing cement to surface the rig crew pulled 12 fts of tubing & the cement crew circulated cement to surface. After pulling the remaining tubing cement crew topped off the well. Used 260 sks cement. Well Plugged

Name of Plugging Contractor: Quest Cherokee Oilfield Service, LLC License #: 33344
 Address: 211 W. 14th Street, Chanute, KS 66720

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Party Responsible for Plugging Fees: Quest Cherokee, LLC
 State of Kansas County, Neosho, ss.
Quest Cherokee, LLC (Employee of Operator) or (Operator) on above-described well, being first duly

SEP 24 2008

CONSERVATION DIVISION
WICHITA, KS

sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Jennifer R. Smith
 (Address) 211 W. 14th Street, Chanute, KS 66720

TERRA KLAUMAN
Notary Public - State of Kansas
My Appt. Expires 8-4-2010

SUBSCRIBED and SWORN TO before me this 22nd day of September, 20 08
Terra Klauman My Commission Expires: 8-4-2010
 Notary Public

[Handwritten initials]