


15-065-02640-00-00

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Graham County, Sec. 22 Twp. 9S Rge. (E) 24 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW%SW%" or footage from lines C NE SE
Lease Owner Abercrombie Drilling, Inc.
Lease Name NICKELSON Well No. 1
Office Address 801 Union Center, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed August 9, 19 63
Application for plugging filed verbally - August 9, 19 63
Application for plugging approved verbally - August 9, 19 63
Plugging commenced August 9, 19 63
Plugging completed August 9, 19 63
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? verbally - yes.

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4065' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	209'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud to 540 feet.
Set 1st Plug at 540' w/20 sx cement through drill pipe.
Set 2nd Plug at 140' w/10 sx cement & 1/4 sx hulls.
Set 3rd Plug at 40' w/10 sx cement & 1/2 sx hulls.

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1963
08 15 1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Abercrombie Drilling, Inc.
Address 801 Union Center, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
B. Lynn Herrington (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Lynn Herrington
801 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 14th day of August, 1963
My commission expires June 16, 1967
Leah Faye Hefke
Leah Faye Hefke Notary Public.



15-065-02640-00-00

CONTRACTOR'S WELL LOG

COMPANY:	Abercrombie Drilling, Inc.
CONTRACTOR:	Abercrombie Drilling, Inc.
FARM:	NICKELSON #1
LOCATION:	C NE SE Section 22-9S-24W Graham County, Kansas
COMMENCED:	July 31, 1963
COMPLETED:	August 9, 1963

0	40	Sand
40	219	Shale
219	1068	Shale & Shells
1068	1255	Shale
1255	1655	Shale & Shells
1655	2115	Sand & Shale
2115	2157	Anhydrite
2157	2386	Shale
2386	2680	Shale & Shells
2680	2872	Shale
2872	3100	Shale & Lime
3100	3243	Shale & Shells
3243	3316	Shale & Lime
3316	3581	Lime
3581	3673	Lime & Shale
3673	4065	Lime
	4065	Rotary Total Depth

RECEIVED
STATE CORPORATION COMMISSION

AUG 15 1963
08-15-1963
CONSERVATION DIVISION
Wichita, Kansas

Set 8-5/8" surface casing at 209' w/150 sx Sunset.

DRY & ABANDONED

SCHLUMBERGER TOPS:

Heebner	3790'	(-1322)	
Lansing	3832'	(-1364)	ELEVATION: 2468' D. F. & K. B.

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, B. Lynn Herrington, do hereby certify that the above and foregoing is a true and correct copy of the log of the NICKELSON #1, C NE SE, Section 22-9S-24W, Graham County, Kansas, as reflected by the files of Abercrombie Drilling, Inc.

B. Lynn Herrington
B. Lynn Herrington

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 14th day of August, 1963.



Leah Faye Hefke
Leah Faye Hefke, Notary Public

My commission expires June 16, 1967.