

15-065-20835-00-00


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Graham County, Sec. 25 Twp. 9 Rge. 25 EW  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SE/SE/SE  
Lease Owner The Maurice L. Brown Company  
Lease Name GUFFEY Well No. 1  
Office Address 1500 Vickers KSB&T Bldg., Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above  
Section Plat

Date Well completed 19  
Application for plugging filed May 25 19 77  
Application for plugging approved 19  
Plugging commenced June 27 19 77  
Plugging completed July 14 19 77  
Reason for abandonment of well or producing formation  
depleted  
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or  
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor  
Producing formation Depth to top Bottom Total Depth of Well 4140'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	233'	none
				5 1/2"	4137'	2,566.78'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid  
was placed and the method or methods used in introducing it into the hold. If cement or other  
plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Dumped sand to 4000' and 5 sacks cement.  
Shot pipe at 3200', 3000', 2800' and 2600'.  
Pulled a total of 69 joints of 5 1/2" casing.  
Plugged well with 3 sacks hulls, 70 sacks 50/50 Pozmix with 6% added gel,  
7 sacks gel and 60 sacks 50/50 Pozmix with 6% added gel.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.  
P.O. Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton ss.  
James W. Rockhold (employee of owner) or (owner or operator) of the above-described  
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the  
above-described well as filed and that the same are true and correct. So help me God.



(Signature) James W. Rockhold  
Box 698, Great Bend, Kansas 67530  
(Address)

RECORDED AND SWORN TO before me this 22nd day of July 19 77

My commission expires May 21, 1980

Marla K. Haslam Notary Public.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 25 1977  
07-25-1977  
CONSERVATION DIVISION  
Wichita, Kansas

CONTRACTOR'S WELL LOG

ANTONINE

JUN 12 1976

OPERATOR: The Maurice L. Brown Company  
 CONTRACTOR: Abercrombie Drilling, Inc.  
 WELL NAME: GUFFEY ESTATE #1  
 LOCATION: SE SE SE Section 25-9S-25W  
 Graham County, Kansas  
 SPUD DATE: May 25, 1976  
 COMPLETION DATE: June 7, 1976

0	234	Surface clay, sand & shale
234	705	Sand & shale
705	1770	Shale & sand
1770	1968	Sand
1968	2209	Shale
2209	2244	Anhydrite
2244	2626	Shale & shells
2626	3208	Lime & shale
3208	3495	Lime & shale
3495	3572	Shale & lime
3572	3879	Lime & shale
3879	4140	Lime
	4140	Rotary Total Depth

Spudded in @ 6:30 p.m. May 25, 1976. Drilled 234' of 12 1/4" hole. Ran 6 joints of 8 5/8" casing, tallied 225.70', Set @ 232.79' with 190 sx. Class "A" cement, 3% ca. cl. Cement did circulate. Welded all collars. Plug was down @ 11:35 p.m. May 25, 1976.

Ran 118 jts. 5 1/2" 14# new and used casing. Set @ 4137' K.B. Cemented with 150 sx. Posmix. Plug was down @ 9:10 p.m. June 7, 1976.

SAMPLE TOPS:  
 Anhydrite 2209'

RECEIVED  
 STATE CORPORATION COMMISSION  
 MAY 26 1977  
 CONSERVATION DIVISION  
 Wichita, Kansas

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

Jerry A. Langrehr, Executive Vice President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the GUFFEY ESTATE #1, SE SE SE Section 25-9S-25W, Graham County, Kansas.

ABERCROMBIE DRILLING, INC.  
 By: Jerry A. Langrehr  
 Jerry A. Langrehr-Exec. V.P.

Subscribed and sworn to before me, a Notary Public, in and for the aforesaid county and state as of this 11th day of June, 1976.

Diane Steincamp  
 Diane Steincamp - Notary Public

My Commission Expires: February 18, 1980

