

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-065-22,056

LEASE NAME SPIES

WELL NUMBER 1

SPOT LOCATION C NW SW

SEC. 26 TWP. 9 RGE. 25 (E) or (W)

COUNTY GRAHAM

Date Well Completed 9-14-84

Plugging Commenced 12-19-84

Plugging Completed 12-19-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR R P NIXON OPERATIONS

ADDRESS 207 W 12TH HAYS KS 67601

PHONE #(913) 628-3834 OPERATORS LICENSE NO. 5252

Character of Well OIL
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? YES

Which KCC/KDHE Joint Office did you notify? HAYS

Is ACO-1 filed? YES If not, is well log attached? _____

Producing formation KANSAS CITY Depth to top 3859' bottom -1297' T.D. 4120'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
SURFACE PRODUCTION		204	surf	8 5/8"	204'	NONE
		4119	surf	4 1/2"	4119'	3060'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Cement with 170 sacks 50/50 pozmix 6% gel, 3% c.c. Mixed 23 sacks gel with 4 sacks hulls-100 sacks cement 17 sacks gel-release plug-70 sacks cement. Max pressure 300% shut in pressure 100%. ---Cemented bottom hole and perforations by spotting 4 sacks common, sanded up to 3900'. Topped out with 4 sacks common cement spotted with bailer.

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SUPERIOR WELL SERVICE License No. _____
Address P O BOX 276 PLAINVILLE KS 67663

STATE OF KANSAS COUNTY OF ELLIS, ss.

DAN A NIXON (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 207 W 12TH

SUBSCRIBED AND SWORN TO before me this 26th day of December, 1984

STATE CORPORATION COMMISSION

Lorna M. Herrman
Notary Public

My Commission expires: 6-19-88 DEC 27 1984

CONSERVATION DIVISION
Wichita, Kansas

LORNA M. HERRMAN
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 6-19-84

Form CP-4 1-84
Revised 06-83