

4-050296

12-10

API Number: 15-193-20,478-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

NE SE SE /4 SEC. 22, 09 S, 32 W  
990 feet from S section line  
330 feet from E section line

Operator license# 6484

Lease: Bertrand Well # 1

Operator: Anderson Energy, Inc.

County: Thomas 152.78

Address: 200 E. 1st St. - Suite #414  
Wichita, Kansas 67202  
316-265-7929

Well total depth 4701 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 279 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Allied Cementing License# -

Address: \_\_\_\_\_

Company to plug at: Hour: P.M. Day: 10 Month: November Year: 1997

Plugging proposal received from: Wally Wahlmeier

Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: 8 5/8" at 279' w/165 sxs.  
5 1/2" at 4700' w/200 sxs.  
Perfs at 4505' - 4512'; 4476' - 4480'; 4463' - 4473'.  
PBTD 4652'.  
610 sxs 60/40 pozmix - 10% gel - 900# hulls.

KANSAS STATE CORPORATION COMMISSION  
RECEIVED  
12-17-1997  
11:30 AM

Plugging Proposal Received by: Marvin Miller

Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour 6:30 P.M. Day: 10, Month: December, Year: 1997

Actual plugging report: Ran tubing to 4000' and pumped 100 sxs cement with 300# hulls. Pulled tubing to 2945' and pumped 100 sxs cement. Pulled tubing to 1860' and pumped 120 sxs cement with 550# hulls - cement circulated. Pulled rest of tubing and tied onto 5 1/2" casing. Squeezed with 290 sxs cement with 50# hulls. Max. P.S.I. 900#. S.I.P. 500#. Backside full cement at surface.

Remarks: \_\_\_\_\_

Condition of casing(in hole): GOOD  BAD  Anhy.plugin: YES  NO

Bottom plug(in place): YES  CALC , NO  Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: \_\_\_\_\_ GL

I did[ ] / did not[ X ] observe the plugging.

Marvin Miller (agent)

INVOICED

DATE DEC 18 1997

INV. NO. 49735