

4-080206

2-22

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
WICHITA, KANSAS 67202

API number: 193-20,657-0000

SW NE NW /4 SEC. 22, 9 S, 32 W
4290 feet from S section line
3630 feet from E section line

Operator license# 5135

Lease Renner well # 3

Operator: John O. Farmer, Inc.

County Thomas

Address: P. O. Box 352
Russell, Kansas 67665

Well total depth 4690 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 288 feet

152.42

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Abercrombie RTD, Inc License# 30684

Address: Wichita, Kansas

Company to plug at: Hour: 1:30 PM Day: 22 Month: February Year: 1997

Plugging proposal received from: Tony

Company: Abercrombie RTD, Inc. phone:

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 2660 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1820 feet " 100 " Mousehole: sacks

3rd plug @ 340 feet " 40 "

4th plug @ 49 feet " wiper plug & 10sx

Plugging Proposal Received by: Bruce D. Basye

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 1:30 PM, Day: 22, Month: February, Year: 1997

Actual plugging report: Hole reported plugged as above.

Order 180 sx 60/40 pozmix w/ 6% gel and 1/4 # celloflake or flowcel per sack.

Remarks: Elevation: 3068 GL, Anhydrite depth: 2651 -2678 feet

Did not penetrate Arbuckle, cemented by Allied

I did[] / did not[X] observe the plugging.

Bruce D. Basye
Bruce D. Basye Geologist
(agent)

OK IM

Form CP-2/3

INVOICED

DATE 3-5-97

INV. NO. 47695

2-22

RECEIVED
KANSAS CORP COM

1997 MAR -4 P 1:24

03-04-1997