

To: 6 100387  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

5-2/  
API NUMBER 15- 15-193-20,479-00-00

SW NW, SEC. 25, T 9 S, R 32 W/EX  
3300 feet from S section line  
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Robben Well # 1

Operator: Raymond Oil Company

County Thomas 149.50

Name & Address Box 48788

Well Total Depth 4600 feet

Wichita, Ks. 67201

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Murfin Drilling License Number 6033

Address Wichita, Ks,

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Rodney Farr

(company name) Murfin Drilling Co. (phone) \_\_\_\_\_

were: Spot plugs through drill pipe w/heavy mud between all plugs.

1st plug at 2620' w/25 sks Rathole 15 sks

2nd plug at 1795' w/100 sks Mousehole 10 sks

3rd plug at 400' w/40 sks

4th plug at 40' w/wiper plug and 10 sks

RECEIVED  
STATE CORPORATION COMMISSION  
JUL - 6 1989  
07-06-1989  
CONSERVATION DIVISION  
Wichita, Kansas  
David K. Wann  
(TECHNICIAN)

Plugging Proposal Received by \_\_\_\_\_

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 10:45 AM Day: 21 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Order 200 sks 60/40 poz w/6% gel and 2 sks Celloflake/  
flowcel. Hole reported plugged as above.

Remarks: Elevation: 3044' KB Anhydrite depth : 2619' Did not penetrate Arb. Cemented by  
(If additional description is necessary, use BACK of this form.) Allied.

~~Do not~~ observe this plugging.

Signed David K. Wann  
(TECHNICIAN)

David K. Wann

DATE 7-7-89

INV. NO. 25248