

5-10

4-041581

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,479-~~200~~-01

C SW NW /4 SEC. 25, 09 S, 32 W
3300 feet from S section line
4620 feet from E section line

Operator license# 3295 Lease Robben well # 2

Operator: David W. Clothier County Thomas

Address: 101 S. Battin Street Well total depth 4700 feet ^{152.75}
Wichita, Kansas 67218 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 355 feet
w/230 sxs.

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Cementing License#

Address: Oberlin, Kansas

Company to plug at: Hour: 10:00P.M Day: 10 Month: May Year: 94

Plugging proposal received from: David W. Clothier

Company: David W. Clothier Phone: 316-684-6839

Were: 4 1/2" casing set @ 4577' w/450 sxs. cement cwc. Perf. @ 4327' - 4508'. Anhy. @ 2620' - W.L.M. 4510' - T.O.F. @ 2700'.
Ordered 175 sxs. 60/40 pozmix - 10% gel with 1/4# F.C. plus 300# hulls.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 1:45P.M., Day: 10, Month: May, Year: 94

Actual plugging report: Hooked-up to 4 1/2" casing. Pumped 25 sxs. cement w/300# hulls, followed with 8 sxs. gel (30 bbls) followed with 125 sxs. cement. Max. 700#. Hooked-up to 8 5/8" S.P. Pressured-up 300# - 1/2 bbl.

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1994
05 25-1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks:
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES X, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING , CASING X. Elevation: GL

I did [X] did not [] observe the plugging. Dennis L. Hamel

INVOICED
DATE 5-26-94
INV. NO. 40490

HD

(agent)
Form CP-2/3

5-10 JUL 06 1994