

6-100417

8-29

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,524-00-00

W2 SE NW /4 SEC. 25, 9 S, 32 W
3300 feet from S section line
3630 feet from E section line

Operator license# 5011 Lease Robbens well # 1

Operator: Viking Resources, Inc. County Thomas

Address: 105 South Broadway Well total depth 4650 feet
Suite 1040 Conductor Pipe: _____ inch @ _____ feet
Wichita, Kansas 67202-4224 Surface pipe 8 5/8 Inch @ 360 feet

151.12

Aband. oil well _____, Gas well _____, Input well _____, SWD _____, D & A X

Plugging contractor: Mallard Drilling Company License# 4958

Address: _____

Company to plug at: Hour: ? Day: _____ Month: _____ Year: _____

Plugging proposal received from: Secretary for drilling company

Company: Mallard Drilling phone: _____

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2610 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1830 feet " 100 " Mousehole: 10 sacks

3rd plug @ 410 feet " 40 "

4th plug @ 40 feet " wiper plug & 10 sx

5th plug @ _____

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:00 pm, Day: 29, Month: August, Year: 1990

Actual plugging report: Hole reported plugged as above.

Order 200sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

Remarks: Elevation: 3034 GL, Anhydrite depth: 2608 - 2640 feet

Did NOT penetrate Arbuckle, cemented by Allied

I did[] / did not[X] observe the plugging.

RECEIVED
STATE CORPORATION COMMISSION
NOV 15 1990

INVOICED
NOV 16 1990

David K. Wann
CONSERVATION DIVISION
Wichita, Kansas

David K. Wann P.I.R.T. II
(agent)

DATE _____
INV. NO. 29980

J.L.S.