

12-17-87

6 020430

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,455-00-00

NW SW, SEC. 33, T 9 S, R 32 W/E

1980 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123-4277

Lease Name Englehardt Well # 1 "B"

Operator: Pickrell Drilling Col  
Name & Address 110 N. Market, Suite 205  
Wichita, Ks. 67202

County Thomas 154.70

Well Total Depth ? 4760 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Pickrell Drilling License Number 5123

Address Same as above

Company to plug at: Hour: AM Day: 17 Month: Dec. Year: 19 87

Plugging proposal received from Gary Christopher

(company name) Pickrell (phone)

were: Order lbs 60/40 pozmix 6 % gel - 3% flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Plugging Proposal Received by Gil Balthazor (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 7:30 PM Day: 17 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT Cir.

1st. plug at 2690' with 25 sks

2nd plug at 1970 with 100 sks F.C.

3rd plug at 330 w/ 40 sks

4th plug at 40 with 10 sx wiper

15 sks in Rathole

STATE CORPORATION COMMISSION  
12-29-1987  
DEC 24 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 1-7-88 Cemented by Allied  
INV. NO. 19405

Signed Gilbert Balthazor (TECHNICIAN)  
Gilbert Balthazor