

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-193-20303-00-00

NE, Sec. 35, T 9 S, R 32 (W)

990 feet from N/E section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7506

Lease Name Leslie Keller Well #72-35

Operator: First Energy
Name & Address 16701 Green Point
Houston Texas

County Thomas

Well Total Depth 4869 feet 158.25

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 322

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address 617 Union center Bldg, Wichita KS

Company to plug at: Hour: 3 PM Day: 14 Month: 3 Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Terry Mcrae

(company name) Murfin Drilling Co. (phone) 316 267-3241

were: order 195 sx. cement 50/50 pozmix 6% gel 3% c.c.

15x hulls 1-8 5/8 plug 15x Flow Seal

Heavy mud between all plugs

Pump cement down drill pipe

Elev. 3073 Anhydrite 2630-76 Arbuckle No.

Dakota 1500
1573 = 1870

Signed Dale H. Balthazor
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 AM Day: 15 Month: 3 Year: 1984

ACTUAL PLUGGING REPORT circulated @ 2630 for 30 mi.

25 SX @ 2630

100 SX @ 1870 mixed with 15x Flow Seal

40 SX @ 370 15x hulls, pushed plug to 40'

10 SX @ 40

10 SX in Rat hole

10 SX in mouse hole

Remarks:

cementing co. Sun

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1984
03-26-1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Dale H. Balthazor
(TECHNICIAN)

INVOICED

DATE 3-29-84

INV. NO. 0972

3-15