

4-27
4-071094

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,622-00-00

NE SE SE /4 SEC. 36, 09 S, 32 W
990 feet from S section line
330 feet from E section line

Operator license# 30407

Lease Nye well # 2

Operator: Black Petroleum Company

County Thomas

Address: P.O. Box 12922
Wichita, Kansas 67277
Thomas E. Black

Well total depth 4626 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 315 feet

150.34

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: White & Ellis Drilling License#

Address: Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 27 Month: April Year: 94

Plugging proposal received from: Judy and Don Demel

Company: White & Ellis Drilling Phone: 316-942-2741

Were: 8 5/8" - 315' S.P. cwc. w/190 sxs. 60/40 pozmix - 2% gel - 3% C.C. By Allied Cement. Elv. @ 3062' - Anhy @ 2616' - Miss well - No circulation problems - Mud condition 61 vis. - 9.3 wt. - 1500 ppm cl. Proposal 190 sxs. 60/40 pozmix - 6% gel and 1 sx. flocele - circulate hole - spot and displace all cement through tubing - heavy mud between all plugs - no arbuckle. 25 sxs. @ 2620' - 100 sxs. w/1 sx. flocele @ 1810' - 40 sxs. @ 360' - 10 sxs. @ 40' - 15 sxs. in rathole (circulate)

Plugging Proposal Received by: Marion J. Schmidt
Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 5:45P.M., Day: 27, Month: April, Year: 94

Actual plugging report: White and Ellis ordered 190 sxs. 60/40 pozmix - 6% gel and 1 sx. flocele. Circulated hole - spotted and displaced all cement through drill pipe - heavy mud between all plugs.

1st. plug @ 2620' w/25 sxs. cement.
2nd. plug @ 1810' w/100 sxs. cement with 1 sx. flocele.
3rd. plug @ 360' w/40 sxs. cement.
4th. plug @ 40' w/10 sxs. cement.
15 sxs. in rathole (circulate)

RECEIVED
STATE CORPORATION COMMISSION
MAY 05 1994
05-05-1994
CONSERVATION DIVISION
Wichita, Kansas

Remarks: By: Allied Cement.
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO
Bottom plug(in place): YES , CALC , NO X Dakota plug: YES X, NO
Plugged through TUBING , CASING D.P. Elevation: 3062 GL

I did [] did not [X] observe the plugging.

Marion Schmidt
(agent)

INVOICED
MAY 05 1994

DATE

INV. NO. 40386

4-27 JUL 06 1994