

4-050236

15-163-01842-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

6-19

API Number: 15- -

C SW SW /4 SEC. 01 , 10 S, 17 W  
660 feet from S section line  
4620 feet from E section line

Operator license# 9346

Lease: Keas Well # 1

Operator: Diehl Oil Inc.

County: Rocks

Address: Box 234  
Hays, Kansas 67601  
913-625-6711

Well total depth 3586 <sup>116.54</sup> feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 160 feet

Aband. oil well , Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Halliburton Services License# -

Address: \_\_\_\_\_

Company to plug at: Hour: P.M. Day: 19 Month: June Year: 1996

Plugging proposal received from: Glenn Diehl

Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: 8 5/8" @ 160 w/150 sxs. - Perfs 3195' to 3526'.  
4 1/2" @ 3584' w/100 sxs. - Elevation 2060' - Anhydrite 1280'.  
2 3/8" @ 3180' w/300 sxs. - PBT 3494'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All  , Part [ ] , None [ ]

Completed: Hour 3:00 P.M. , Day: 19 , Month: June , Year: 1996

Actual plugging report: Pumped 50 sxs 60/40 pozmix - 10% gel and 300# hulls down 2 3/8" tubing. Max. P.S.I. 2800#. S.I.P. 1300#. Shot tubing at 922' pulled one joint - pumped 70 sxs cement and 200# hulls - cement circulated. Tied onto backside - squeezed with 50 sxs at 225 Max. P.S.I. S.I.P. 100#. Pulled tubing - squeezed casing with 30 sxs. Max. P.S.I. 400#. S.I.P. 150#.

RECEIVED  
KANSAS STATE CORPORATION COMMISSION

JUL 02 1996

7-2-96

Remarks: \_\_\_\_\_  
Condition of casing(in hole): GOOD \_\_\_\_\_ BAD \_\_\_\_\_ Anhy. plug: YES  NO \_\_\_\_\_  
Bottom plug(in place): YES \_\_\_\_\_, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES  , NO \_\_\_\_\_  
Plugged through TUBING \_\_\_\_\_, CASING \_\_\_\_\_ Elevation: 1843 \_\_\_\_\_ GL

I did  / did not  observe the plugging.

Mawin Miller (agent)

Form CP-2/3

INVOICED

DATE 7-5-96

INV. NO. 45946

6-19