

6 070520

PLUGGED

15

API NUMBER 15-163-20-219-00-00

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW-SW-NW, SEC. 1, T. 10 S, R. 17 W E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 6566

Lease Name KLIM Well # 1

Operator: Leben Oil Corporation

County Rocks 115.05

Name & Address P.O. Box 21468

Well Total Depth 2540 feet

Tulsa, Oklahoma 74121

Conductor Pipe: Size 0 feet

1468

Surface Casing: Size 8 5/8" feet 209

Glenn Jackson

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor B.J. Titan License Number

Address Hays, Kansas 67601

Company to plug at: Hour: 2:00 PM Day: 3RD Month: Nov. Year: 19 86

Plugging proposal received from John Glenn

(company name) Kaiser Francis oil Co (Leben) (phone) 918-494-0000

were: 8 5/8" - 209^{ET} SP. cas. 11/150^{SK} cmt., 5 1/2" csg set @ 2528^{ET} 11/150^{SK} cmt.

Perf's 3160' to 3432', well in good condition, at Bottom Sand to 3060 and 1/5^{SK} cmt.

Kelso put stretch on csg. csg parted @ 2881^{ET}, Gordon unit, Ran tubing couldn't get back in csg.

(Recovered 2881^{ET} 5 1/2" csg) operator Ran Impression Block, and Wall Hook, 5 1/2" csg pushed to side.

Operator's Proposal Run tubing (wash down) as far as possible, Circulate Cement to Surface

then squeeze from top 11/150^{SK} cmt.

Plugging Proposal Received by Marion Schmidt

Ordered 275^{SK} 6 1/4 Pozmix + Gel - Ca. Cl. - and 6^{SK} shells and 11^{SK} GD. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:30^{PM} Day: 3RD Month: Nov. Year: 19 86

ACTUAL PLUGGING REPORT Ordered 275^{SK} 6 1/4 Pozmix + Gel - Ca. Cl., 11^{SK} GD, and

5^{SK} shells. Ran in 2 3/8" tubing and washed down to 409^{ET}.

@ 409 ft. spotted 125^{SK} cmt. cmt. Circulated. 11-10-86

Layed down Tubing. NOV 10 1986

with pump truck pumped in 8 5/8" csg. another 150^{SK} cmt. (squeeze)

max. pressure 850 Psig - shut in pressure 450 Psig.

Remarks: Cemented by B.J. Titan.

(If additional description is necessary, use BACK of this form.) 11-6-86

INVOICED

Do not observe this plugging.

DATE 11-12-86

Signed Marion Schmidt (TECHNICIAN)

INV. NO. 15329