

6 030806

PLUGGED

OCT 31 1986

API NUMBER 15-163-20225-0000

1700 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SESWING SEC. 1, T 10 S, R 17 W

2970 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6566

Lease Name KLIM Well # 2

Operator: LEBEN OIL CORP.

County ROOKS 114.40

Name & Address P.O. Box 21468

Well Total Depth 3520 feet

TULSA, OKLAHOMA

Conductor Pipe: Size \_\_\_\_\_ feet

74121-1468

Surface Casing: Size 8 7/8 feet 200'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor KELSO CASING License Number 6050

Address CHASE KANSAS

Company to plug at: Hour: AM Day: 31 Month: 10 Year: 19 86

Plugging proposal received from CLAY

(company name) KELSO CASING (phone) \_\_\_\_\_

were: 8 7/8 SET @ 200' w/ 150 SX. 5 1/2 SET @ 3518' w/ 150 SX PBD 3520.

TOP PERF. 3148 ORDER SAND & COM. CNT. PULL PIPE ORDER 150 SX.

THRIFTY MIX 65/35 PZ 10% GEL 2% DICE 4 SX. HULLS B.J. TITAN CNT. CO.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 9:30 AM Day: 31 Month: 10 Year: 19 86

ACTUAL PLUGGING REPORT Dump SAND ON PBD 3520 TO 3100+ SPOT 5 SX.

COM. CNT. ON SAND WITH BAILER. SHOT & PULLED 1900' 5 1/2" CSG. (5 SHOTS)

TIE ON TO 8 7/8" MIX. & PUMP 4 SX. HULLS + 100 SX. CNT. MIX.

MAX. PST 800' CLOSE IN 300' PLUG COMPLETE.

12-9-86

STATE CORPORATION COMMISSION

DEC 8 1986

Remarks: (If additional description is necessary, use BACK of CONSERVATION DIVISION Wichita, Kansas 11-21-86

INVOICED

did (or did not) observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 12-9-86

INV. NO. 15548