

To: 6 041040
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

5-24 15-11-12-69
API NUMBER 15- 11-12-69

NE NW SW, SEC. 1, T 10 S, R 17 WAE

feet from S section line

feet from E section line

TECHNICIAN'S PLUGGING REPORT

3613

Operator License #

Lease Name Keas Well # 3

Operator: Quinoco Pet Inc.

County Rooks 114.69

Name & Address

Well Total Depth 3529 feet

915 Patton Rd.

Conductor Pipe: Size feet

Great Bend, Ks. 67530

Surface Casing: Size 8 5/8 feet 209 w/125 sks

Abandoned Oil Well ☒ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☐

Other well as hereinafter indicated

Plugging Contractor Halliburton Cementing License Number

Address Hays, Ks. 67601

Company to plug at: Hour: 8:00 AM Day: 24 Month: May Year: 19 89

Plugging proposal received from George Hutton

(company name) Quinoco Pet. Inc. (phone)

were: 4 1/2" casing set at 3528' w/200 sks. Top perf at 3192'

Sq at 2565' - 75', 2060', 825' - 1056'. Top anhy 1260'. Ordered 300 sks 65/35 pzo 10% gel w/1/4# f.c. plus 500# hulls.

RECEIVED
STATE CORPORATION COMMISSION

JUN 6 1989

66-89
Plugging Proposal Received by Dennis Hamel (TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part ☐ None ☐

Operations Completed: Hour: 11:45 AM Day: 24 Month: May Year: 19 89

ACTUAL PLUGGING REPORT Ran tubing 925' - pumped 50 sks thru tubing. Pulled tubing.

Pumped in 4 1/2" casing 200 sks cement w/1/4# f.c. plus 350 hulls, mixed in cement.

Max 600# S.I. 100# psi. Pumped in 8 5/8" casing 40 sks cement w/1/4# f.c. plus 50# hulls

mixed in cement. Max 500# S.I. 400# psi. (W.I.M. 965'. Ran tubing to 925' - bad casing.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED
DATE 6-8-89
WV. NO. 25014
5-24

Signed Dennis L. Hamel (TECHNICIAN)
Dennis Hamel