

6 020409

9-29  
API NUMBER 13- 163-22, 947-00-00

To: State Corporation Commission  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

E/2 E/2 NE, SEC. 5, T. 10 S, R. 16 W/E  
3960 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5068

Lease Name Krysl Well # 1

Operator: Black Petroleum Co.  
Name & Address: 527 Union Center  
Wichita, Kansas  
316-264-9342

County Rooks 115.34  
Well Total Depth 3549 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 259 150 sks

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Emphasis Oil Oper. License Number 8241

Address Russell, Kansas

Company to plug at: Hour: \_\_\_\_\_ AM Day: 29 Month: Sept Year: 19 87

Plugging proposal received from Tom Olm

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: Order 175 sks 60/40 Pozmix 6% Gel 1 sk Flocele and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis mud between all plugs with good circulation and no fluid loss.

Plugging Proposal Received by Gil Balthazor  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 4:45 AM Day: 29 Month: Sept Year: 19 87

ACTUAL PLUGGING REPORT Cir Mud between all plugs

1st plug at 3440' w/25 sks

2nd plug at 1230' w/25 sks

3rd plug at 700' w/100 sks F. C.

4th plug at 40' w/10 wiper.

15 sks in rat hole 10 sks in mouse hole.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 23 1987  
10-23-87  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Cemented by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If desired, oil and gas) observe this plugging.

DATE 10-26-87

INV. NO. 18650

Signed Gilbert Balthazor  
(TECHNICIAN)  
Gilbert Balthazor