

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-22931-00-~~00~~⁰¹ *Kee NR*
Spot: CNWSESW Sec/Twnshp/Rge: 5-10S-16W
990 feet from S Section Line, 3630 feet from E Section Line
Lease/Unit Name: COLLINS Well Number: 1
County: ROOKS Total Vertical Depth: 3580 feet

Operator License No.: 5011
Operator Name: VIKING RESOURCES, INC
Address: 105 S BROADWAY, STE 1040
WICHITA, KS 67202

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 250
Production: Size 4.5 feet: 3314 *116.35*
Liner: Size _____ feet:

9/12

Well Type: SWD UIC Docket No: D-26165 Date/Time to Plug: 9/12/00 9:00:00 AM
Plug Co. License No.: 5011 Plug Co. Name: VIKING RESOURCES, INC
Proposal Rcvd. from: JAMES B. DEVLIN Company: VIKING RESOURCES, INC Phone: (316) 262-2502

Proposed 4 1/2" casing set at 3314' w/90 sxs cmt. Perf at 3550' - 3565'.
Plugging D.V. Anhy. @ 1242' w/715 sxs.
Method: Ordered 150 sxs 60/40 pozmix - 10% gel - 15 sxs gel - 500# hulls.

Plugging Proposal Received By: DENNIS HAMEL Witness Type: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 09/12/2000 2:00 PM KCC Agent: DENNIS HAMEL

Actual Plugging Report:

Rigged up cementers to 4 1/2" casing and squeezed as follows: 50 sxs cement w/500# hulls, followed with 15 sxs gel, followed with 75 sxs cement. Max. P.S.I. 1000#. S.I.P. 800#.
Rigged up cementers to 8 5/8" S.P. and pressured up S.P. to 600#.
Job complete.

RECEIVED
STATE CORPORATION COMMISSION
9-22-00
SEP 22 2000

Remarks:

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: CSG

District: 04

Signed

Dennis J. Hamel

(TECHNICIAN)

B

INVOICED

DATE

9/25/00

INSTR. NO.

2001060730

Form CP-2/3

SEP 18 2000

BLACK PETROLEUM COMPANY
WICHITA, KS 67202

5-10 -16W
NW SE SW

#1 COLLINS

site: 3/4 N & 1-3/4 E OF CODELL, KS
contr: EMPHASIS OIL OPERATIONS
geol: MARVIN DOUGLAS

city: ROOKS
field: WC (3/4 W OF CONGER)

API 15-163-22931

fr date 06/16/87 spd date 06/15/87 drlg comp 06/23/87 card issued 04/13/88 last revised 04/13/88

ELV: 2019 KB LOG

tops.....	depth/datum
ANH.....	1217 +802
B/ANH.....	1252 +767
STOT.....	2705 -686
TARK.....	2761 -742
HOW.....	2881 -862
TOP.....	2909 -890
KH.....	3013 -994
QH.....	3070 -1051
HEEB.....	3137 -1118
TOR.....	3151 -1132
LANS.....	3182 -1163
STARK.....	3382 -1363
BKC.....	3431 -1412

IP status:

D & A, ARB ,
CSG: 8-5/8" 250 / 150 SX, 4-1/2" 3350
NO CORES
DST (1) 3206-3230 (LKC), / 30-30-45-60, REC 310' MW
ISIP 980# FSIP 1002# IFP 54# -75# FFP 118# -151#
BHT 108'

MARM.....	3462 -1443
CONG.....	3508 -1489
ARB.....	3563 -1544
LTD.....	3568 -1549
RTD.....	3569 -1550

(over)

COPYRIGHT 1988
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS